

FILED

Date: 1-18-2018 By: JC

This survey consists of:

Map: \_\_\_\_\_

Narrative: \_\_\_\_\_

Corner Rpt: CS 65/95-49

DOUGLAS COUNTY  
SURVEYOR

CORNER REPORT FORM

Section 36 Township 23S Range 8W  
Douglas County Date 7/11/2017  
PLSS Number 600200

CORNER DESIGNATION

NW corner of SEction 36.

- \_\_\_ Condition Report only
- \_\_\_ Not Found
- X Renewed
- \_\_\_ Unrecorded
- \_\_\_ Surveyed In
- \_\_\_ Referenced out

Previous Renewals/Surveys, etc:

Original 1857 by Hathorn. 1893 G.L.O. survey by Whipple. 1964 B.L.M. survey by Brooks and Peterson. 1984 B.L.M. survey by Malloy. 2014 renewal by D.C.S.

Monument(s) & Accessories Found: (Condition and Source)

Found 1964 B.L.M. brass cap in good condition.  
 A 25" diam., 2' tall Maple stump ( 1893 B.T. ) bears S. 72° W., 42.2'  
 An 18" ( record 25" ) Fir with healed blaze bears N. 74° E., 33.7' ( 1964 B.T. )  
 A 17" diam., 5' tall Fir stump w/healed blaze bears N. 84° W., 57.4' ( 1964 B.T. )  
 The 2014 Fir bearing S 45° E. is now a blowdown.  
 The 1/2" diam. iron rod remains as noted in 2014.  
 Immediately West and South of this corner is a clearcut.

Monument Detail

Sketch

Standard B.L.M. brass cap.

Monument Set (Procedures and Description)

N/A

New Accessories

Set 6 foot steel posts 2 feet North, South and East.

Surveyor's Seal

Location & Comments

Compass Declination 15° East


Firm/Agency: David Edwards Land Surveying

Address: P.O. Box 361  
Oakland, Oregon 97462


Party Chief: Brant Miller

Notes: \_\_\_\_\_

Witness: Eric Sprinkle



*David A. Edwards*



Renews 12/31/17

C.S. File 65/95-49