

FILED

Date: 1-18-2018 By: sc

This survey consists of:

Map: _____

Narrative: _____

Corner Rpt: CS 65/95-50

DOUGLAS COUNTY
SURVEYOR

CORNER REPORT FORM

Section 36 Township 23S Range 8W
Douglas County Date 7/11/2017
PLSS Number 620200

CORNER DESIGNATION

West 1/16 corner common to
Sections 25 and 36.

- ___ Condition Report only
- ___ Not Found
- X Renewed
- ___ Unrecorded
- ___ Surveyed In
- ___ Referenced out

Previous Renewals/Surveys, etc:

Originally set by the B.L.M. in 1964.

Monument(s) & Accessories Found: (Condition and Source)

Found 1964 B.L.M. brass cap in good condition.

The 1964 B.L.M. Fir bearing N. 67 1/2° W. is gone.

A 29" diam., 3' tall Fir stump with healed blaze bears S. 51 1/2° W., 46.2' (1964 B.T.)

Monument Detail

Sketch

Standard B.L.M. brass cap.

Monument Set (Procedures and Description)

N/A

New Accessories

- A 6" diam. Fir scribed "W 1/16 S36 BT" bears S. 27° E., 2.8'
- A 12" diam. Fir scribed "W 1/16 S25 BT" bears N. 72° W., 21.7'
- A six foot steel post is set 2 feet East.

Surveyor's Seal

Location & Comments

Compass Declination 15° East

Firm/Agency: David Edwards Land Surveying


Address: P.O. Box 361

Oakland, Oregon 97462

Party Chief: Brant Miller

Notes: _____

Witness: Eric Sprinkle



Renews 12/31/17

C.S. File 65/95-50