


HERZSTEIN LAND SURVEYING
OREGON PROFESSIONAL LAND SURVEYOR
 541-679-9872
 2002leonard@gmail.com



Leonard E. Herzstein, LS 2150
 1741 Byron Creek Road
 Winston, OR 97496

**Renewal of NE Corner of Donation Land Claim No. 38, T. 29 S., R. 7 W., W.M.
 Point ID #038010**

Corner Evidence Found:

June 20, 2018

At the corner point, I found a 5"x5" sandstone, firmly set, projecting 12" above the ground, marked "C 38" on the westerly side.

From which bearing trees marked by Douglas County Surveyor's Office in 1998 C.S. File 64/79-4:

- An 11" white oak, bears N. 82° E., 42.9 feet, with a healed double blaze.
- A 15" Douglas fir, bears N. 22° E., 16.9 feet (rec. 16.7 ft. per C.S. File 64/79-4), with a healed double blaze.
- An 8" white oak, bears N. 60° W., 28.3 feet (rec. 28.5 ft. per C.S. File 64/79-4), with a healed double blaze.

Perpetuation of Corner:

June 20, 2018

I set a new bearing object:

- A 1/2" diameter iron rod, 24" long, driven 20" into the ground with a yellow plastic cap (YPC) affixed, stamped "HERZSTEIN - LS 2150", bears N. 84° 50' E., 89.74 feet.

I turned angles with a Lietz optical transit based on a traverse westerly on the DLC line, which has a platted bearing of N. 89° 09' 29" W., as this basis of bearings. BT bearings are reported to the nearest 15 minutes. The YPC bearing is reported to the nearest 01 minute. Trees are measured to the center of the root crown. Tree diameters are at breast height.

8/02/02 3MNC

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

LBA

OREGON
 JULY 26, 1985
 LEONARD E. HERZSTEIN
 2150

CURRENT CERTIFICATE
 RENEWS: JUNE 30, 2019

FILED
 Date: 7-11-2018 Rv. JC
 This survey consists of:
 Map: _____
 Narrative: _____
 Corner Rpt: CS 65/101-2

**DOUGLAS COUNTY
 SURVEYOR**

C.S. FILE 65/101-2