

FILED

Date: 7-18-2018 By: SC

This survey consists of:

Map: \_\_\_\_\_

Narrative: \_\_\_\_\_

Corner Rpt: CS 65/101-43

DOUGLAS COUNTY  
SURVEYOR

CORNER REPORT FORM

Section 2 & 3 Township 32S Range 7W  
Douglas County Date 02/20/2018  
PLSS Number 500640

CORNER DESIGNATION

1/4  
S 3 | S 2

- \_\_\_ Condition Report only
- \_\_\_ Not Found
- X Renewed
- \_\_\_ Unrecorded
- \_\_\_ Surveyed In
- \_\_\_ Referenced out

Previous Renewals/Surveys, etc:

June 1964 BLM established at proportionate distance, April/June 1982 renewed by BLM.

Monument(s) & Accessories Found: (Condition and Source)

2-1/2" Brass Cap on 2-1/2" iron pipe set in cut slope of logging skid road from which a:  
-13" D. fir stump badly rotten bears S 31° W 32.0'  
-12" D. fir stump badly rotten bears N 70° W 16.2'

Monument Detail

Sketch



Monument Set (Procedures and Description)

New Accessories

New BTs

- 10" D. fir scribed "1/4 S2 BT" bears S 71° E 15.2'
- 10" D. fir scribed "X BT" bears S 9° E 16.1'
- 8" D. fir scribed "1/4 S3 BT" bears S 48° W 18.5'
- 5/8" x 30" iron rod w/ plastic cap marked "LAND MARK  
PLS2287" bears S 74° W 9.2'

Location & Comments


OREGON COORDINATE  
REFERENCE SYSTEM,  
COTTAGE GROVE -CANYONVILLE  
ZONE,  
NAD 88-(2011),  
EPOCH 2010 PER GPS  
OBSERVATION HOLDING NGS  
CORS STATIONS "RSBG" & "DDSN"  
Lat. N43°09'04.8999"  
Long. W123°37'47.4072"

Compass Declination 16°  
Firm/Agency: Land Mark Surveying, Inc  
Address: P.O. Box 13  
Roseburg, OR 97470  
Party Chief: Bartt Heichel  
Notes: \_\_\_\_\_  
Witness: Anthony Welch

Surveyor's Seal



*Mark A. Heimbarger*



*Renews 6/30/19*

C.S. File 65/101-43