

# OREGON CORNER RESTORATION FORM

SECTION 19 TOWNSHIP 20 S. RANGE 11W  
COUNTY DOUGLAS DATE 2/1/2019 TRACT PERKINS CREEK  
POINT IDENTIFIER 120400

**CORNER DESIGNATION:**

T 20 S R 11 W  
S18  
W1/16 —○—  
S19

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

**FILED**  
Date: 4/16/2019 By: E  
This survey consists of  
Map: \_\_\_\_\_  
Narrative: \_\_\_\_\_  
Corner Rpt: CS65/102-27

**PREVIOUS RENEWALS/SURVEYS, ETC:**


W1/16 CORNER BETWEEN SECTION 18 & 19 WAS SET BY HOOTMAN IN MAP M24-52. REFERENCED BY HOOTMAN IN MAPS M22-26, AND BY MINOR IN MAPS M116-56 & M125-26.

**DOUGLAS COUNTY SURVEYOR**

**ACCESSORIES FOUND: (CONDITION AND SOURCE)**


14" HEAVILY DECAYED HEMLOCK STUMP BEARS N42°W 8.6 FT. AS PER RECORD BT TAG ON STUMP  
19" HEAVILY DECAYED HEMLOCK STUMP BEARS S84°W 24.9 FT. AS PER RECORD FOUND BT TAG ON GROUND  
AND WE NAIL TO STUMP

**MONUMENT DETAIL:**



**LEGEND:**

- FND HOOTMAN IRON PIPE PER MAP M24-52



**MONUMENT:**

FOUND 1 1/2" IRON PIPE SET BY HOOTMAN IN MAP M24-52

**NEW ACCESSORIES:**

9" DOUG FIR BEARS N69°E 14.95FT. WE SCRIBE W1/16 S18 BT AND TAG TREE  
9" DOUG LIR BEARS S74°W 19.2 FT. WE SCRIBE W1/16 S19 BT AND TAG TREE

**LOCATION & COMMENTS:**

WE FOUND A 1 1/2" IRON PIPE 0.4 FEET ABOVE GROUND  
ON STEEP NORTHERLY SLOPE AND APPROX. 45 FEET  
EAST OF THE EAST EDGE OF WESTERLY POWERLINE R/W.

BEARING BASIS: MAGNETIC BEARING FROM  
HAND COMPASS 16° E DECLINATION  
FIRM/AGENCY: LONE ROCK TIMBER MANAGEMENT CO.  
ADDRESS: P.O. BOX 1127  
ROSEBURG, OR 97470  
PARTY CHIEF: KEN W. HOFFINE  
NOTES: GARY ANGIOLET  
WITNESS: IGNACIO ROMAN

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Ken W Hoffine*

OREGON  
JULY 16, 1987  
KEN W. HOFFINE  
PLS 2291

C.S. FILE 65/102-27

EXPIRES 6-30-19