

# OREGON CORNER RESTORATION FORM

SECTION 6 TOWNSHIP 23 S. RANGE 5W  
COUNTY DOUGLAS DATE 6/28/2019 TRACT J23-5-6 / BECKLEY  
POINT IDENTIFIER 160700

**CORNER DESIGNATION:**

E 1/16TH  
S6  
T23S R5W

CONDITION REPORT ONLY  
 NOT FOUND  
 RENEWED  
 UNRECORDED  
 SURVEYED IN  
 REFERENCED OUT

**FILED**  
Date: 10/15/2019 By: X  
This survey consists of:  
Map: \_\_\_\_\_  
Narrative: \_\_\_\_\_  
Corner Rpt: CS 65/104-14

**PREVIOUS RENEWALS/SURVEYS, ETC:**

1960 HAINES MAP 19-6

**DOUGLAS COUNTY  
SURVEYOR**


**ACCESSORIES FOUND: (CONDITION AND SOURCE)**

NONE

**MONUMENT DETAIL:**



**SKETCH:**  
(NOT TO SCALE)



**LEGEND:**

- LINES BLAZED, PAINTED, POSTED AND TAGGED
- FND 1960 HAINES T-IRON PER M 19-6
- FND 1958 DCSO BRASS CAP
- EXISTING FENCE LINE PORTIONS DOWN

**MONUMENT:**

FOUND 1960 HAINES T-IRON AND BRASS WASHER

**NEW ACCESSORIES:**

- 14" DOUGLAS-FIR BEARS S12 3/4"W 17.1 FT. WE SCRIBE E 1/16 S6 BT AND TAG.
- 17" DOUGLAS-FIR BEARS S 69 1/2"W 46.8 FT. WE SCRIBE E 1/16 S6 BT AND TAG.
- 5 1/2 FT. GALVANIZED U-POST 1.0 FT NORTH.

**LOCATION & COMMENTS:**

WE RAN A RANDOM CLOSED LOOP TRAVERSE BEGINNING AT THE CORNER OF SECTIONS 31 & 32, TRAVERSING WESTERLY TO THE EAST 1/16TH CORNER OF SECTION 6, A HAINES T-IRON. WE THEN TOOK DIRECT GPS OBSERVATIONS OF BOTH MONUMENTS AND ROTATED OUR SURVEY TO THE GPS BEARING, WHICH IS IN THE OCRS LDP ZONE COTTAGE GROVE -CANYONVILLE NAD 83, PROJECTION. WE THEN BLAZED, PAINTED, FLAGGED, POSTED WITH 5 1/2 FT. UPOSTS, AND TAGGED TRUE LINE. CORNER LIES IN DRAW AT THE JUNCTION OF SOUTH-EAST, WEST, AND SOUTH RUNNING FENCELINES

**BEARING BASIS:** FROM DIRECT GPS OBSERVATION OF SECTION 31 AND 31 CORNER AND HAINES T-IRON E1/16TH CORNER  
**FIRM/AGENCY:** LONE ROCK TIMBER MANAGEMENT CO.  
**ADDRESS:** P.O. BOX 1127 ROSEBURG, OR 97470  
**PARTY CHIEF:** KEN W. HOFFINE  
**NOTES:** DANIEL SAILY  
**WITNESS:** IGNACIO ROMAN

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR  
*Ken W. Hoffine*  
OREGON  
JULY 16, 1987  
KEN W. HOFFINE  
PLS 2291

EXPIRES 6-30-21 C.S. FILE 65/104-14