

FILED

Date: 5/14/2020 By: JC

This survey consists of:

Map: _____

Narrative: _____

Corner Rpt: CS 65/106-15

CORNER INVESTIGATION REPORT

DOUGLAS COUNTY
SURVEYOR

FS INDEX ID: U-21

CORNER: SOUTH 1/16 GCDB ID: 600220 DATE: 2/10/2020

TOWNSHIP: 31 S STATE: OREGON

RANGE: 2 W COUNTY: DOUGLAS

SECTION: 25 & 26 FOREST: UMPQUA

MERIDIAN: WILLAMETTE DISTRICT: TILLER

NFSL PROPERTY BOUNDARY CORNER?: YES NO

LINE(S) POSTED: EAST - 1972 WEST - 1972

MAINTAINED: EAST - 1981 WEST - 2018

GUARD POST(S): WEST - 6.5 FT

CORNER HISTORY:

(1) ESTABLISHED CORNER BY SURVEY, SET IRON PIPE/BRASS CAP WITH 2 BT'S.

MONUMENT FOUND/SET:

A 2-1/2" ALUMINUM PIPE WITH A 3" ALUMINUM CAP, PROJECTING 5 INCHES ABOVE A COLLAR OF STONE.

RECORD CORNER ACCESSORIES:

NO TRACE FOUND OF A (1)9" FIR

A 21" FIR BEARS, S43°30'W - 40.4 FT, WITH A HEALED DOUBLE BLAZE.

NEW CORNER ACCESSORIES:

A 14" FIR BEARS, S62°15'E - 11.8 FT, MARKED "S1/16S25" "BT" ON A DOUBLE BLAZE.

NEW BT'S INCLUDE A 3/4" BRASS WASHER MARKED "OR PLS 89396" NAILED FLUSH IN THE LOWER BLAZE BETWEEN THE "B" & "T" MARKS.

CORNER MAINTENANCE/OTHER INFO:

CLEAR BRUSH FROM AROUND MONUMENT & TO BT'S, BT FACES & A 6" BAND AT HEAD HEIGHT PAINTED RED. ADD NEW NAILS TO BT TAGS & ADD NEW TAGS WHERE NEEDED. MONUMENT SIZES ARE OUTSIDE DIAMETER & BT DIAMETERS ARE AT BREST HEIGHT.

NFSL LINES BEAR: (1)S89°52'34"E - 2676.18 FT & (1)S89°48'19"W - 2644.77 FT

GEODETIC COORDINATES:

LATITUDE: N 42° 50' 48.798"

LONGITUDE: W 122° 54' 11.623"

ELLIPSOID HEIGHT:

DATUM: WGS84

SOURCE: USFS OWNERSHIP GIS LAYER, FOR NAVIGATION TO THE CORNER.

DATE OF INVESTIGATION: 5/15/2018

REPORT BY: JONATHAN B. DREW II, PLS# 89396

FIELD CREW: JONATHAN B. DREW II, USFS LAND SURVEYOR
JACOB HUNT, USFS SURVEY TECH
ANDREW HILLMAN, USFS SURVEY TECH

DOCUMENTS ON FILE AT:

WILLAMETTE NATIONAL FOREST
3106 PIERCE PARKWAY, STE D
SPRINGFIELD, OREGON 97477

HISTORY OF VISITATIONS:

(1) 1972 - W.S. BARNES, M42-69 & M42-77

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Jonathan B. Drew II

OREGON
DECEMBER 3, 2014
JONATHAN B. DREW II
89396

EXPIRES: 6/30/2021

RECORD MEASUREMENTS:


(1)N71°30'E - 12.9 FT

(1)S43°30'W - 40.3 FT

METHOD OF MEASUREMENT:

TRIMBLE S7 TOTAL STATION,
HOLD RECROD BEARING, S43°30'W, TO
THE CENTER OF THE SOUTHWEST BT.
BEARINGS MEASURED TO CENTER AND
DISTANCES MEASURED TO AN
ALUMINUM NAIL SET AT SIDE CENTER.

CAP DIAGRAM:



C.S. FILE 65/106-15