

FILED

Date: 5/14/2020 By: JC

This survey consists of:

Map: _____

Narrative: _____

Corner Rpt: CS 65/106-18

CORNER INVESTIGATION REPORT

DOUGLAS COUNTY
SURVEYOR

FS INDEX ID: Z-18

CORNER: WEST 1/16 GCDB ID: 520100 DATE: 2/10/2020

TOWNSHIP: 31 S STATE: OREGON

RANGE: 2 W COUNTY: DOUGLAS

SECTION: 35 ONLY FOREST: UMPQUA

MERIDIAN: WILLAMETTE DISTRICT: TILLER

NFSL PROPERTY BOUNDARY CORNER?: YES NO

LINE(S) POSTED: NORTH - 1972 WEST - 1972

MAINTAINED: NORTH - 2018 WEST - 1981

GUARD POST(S): NORTH - 7.3 FT WEST - 8.0 FT

CORNER HISTORY:

- (1) ESTABLISHED CORNER, SET IRON PIPE/BRASS CAP & 2 BT'S.
- (2) FOUND IRON PIPE/BRASS CAP & 2 BT'S.
- (3) FOUND IRON PIPE/BRASS CAP & 2 BT'S, MARKS 1 NEW BT.

MONUMENT FOUND/SET:

A 2-1/2" IRON PIPE WITH A 3" BRASS CAP, PROJECTING 1 INCH ABOVE THE GROUND.

RECORD CORNER ACCESSORIES:

- A 28" FIR WITH A HEALED DOUBLE BLAZE.
- AN INDETERMINATE SIZED BURNED MADRONE STUMP WITH NO MARKS VISIBLE.
- A 17" FIR WITH A HEALED DOUBLE BLAZE.

NEW CORNER ACCESSORIES:

NO NEW ACCESSORIES ADDED.

CORNER MAINTENANCE/OTHER INFO:

CLEAR BRUSH FROM AROUND MONUMENT & TO BT'S, BT FACES & A 6" BAND AT HEAD HEIGHT PAINTED RED. ADD NEW NAILS TO BT TAGS & ADD NEW TAGS WHERE NEEDED. MONUMENT SIZES ARE OUTSIDE DIAMETER & BT DIAMETERS ARE AT BREST HEIGHT.

NFSL LINES BEAR: (1)N00°05'33"W - 2680.57 FT & (1)N89°02'45"W - 1310.60 FT

GEODETIC COORDINATES:

LATITUDE: N 42° 49' 42.888"

LONGITUDE: W 122° 55' 04.531"

ELLIPSOID HEIGHT:

DATUM: WGS84

SOURCE: CONSUMER GRADE GPS, FOR NAVIGATION TO THE CORNER.

DATE OF INVESTIGATION: 05/16/2018

REPORT BY: JONATHAN B. DREW II, PLS# 89396

FIELD CREW: JACOB HUNT, USFS SURVEY TECH
ANDREW HILLMAN, USFS SURVEY TECH

DOCUMENTS ON FILE AT:

WILLAMETTE NATIONAL FOREST
3106 PIERCE PARKWAY, STE D
SPRINGFIELD, OREGON 97477

HISTORY OF VISITATIONS:

- (1) 1972 - W.S BARNES, M42-72
- (2) 1981 - J. LANDRUM, USFS CORNER CARD
- (3) 1985 - M.E. FARR, USFS CORNER RECORD

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Jonathan B. Drew II

OREGON
DECEMBER 3, 2014
JONATHAN B. DREW II
89396


EXPIRES: 6/30/2021
RECORD MEASUREMENTS:

- (1)N60°E - 12.8 FT, (3)12.5 FT
- (1)S10°E - 8.1 FT, (3)7.5 FT
- (3)N27°30'E - 44.7 FT

METHOD OF MEASUREMENT:

NO NEW MEASUREMENTS TAKEN,
FILED AS CONDITION REPORT.

CAP DIAGRAM:



THIS DOCUMENT FILED IN CS OFFICE: YES
OTHER DOCUMENT FILED WITH CS: NONE

C.S. FILE 65/106-18