

GOVERNMENT CORNER RESTORATION FORM

Date: 4-23-1999 By: JC

Township 22S Range 7W Sec. 19 County DODGE

This survey consists of:

State OK Date 1-28-1999 No. 200300.012

Map:

Narrative:

Corner Rpt: 66/8-12

Corner Designation

519 | 520

530 | 529

DOUGLAS COUNTY

- Condition: Survey Only
Not Found
Renewed
Unrecorded
Surveyed In
Referenced Out

Previous Renewals 1958 DCSO

Monument(s) Found: (Condition and Source)

2 1/2" DIA BRASS CAPON A
1 1/2" O.D. IRON PIPE, PATENTED
1/4" ABOVE GROUND (1958)

COUNTY SURVEYORS OFFICE

T 27S

519 | 520

530 | 529

R 7W

1958

Accessories Found:

24" NOW ROTTED OAK REMAINS AT REC. "S15°W, 71.2 FT"
(CHECKS WITH REC.) OBT.

20" NOW 99" DIA B OAK WITH A HEALED BLAZE
BEARS N45°W, 66.0 FT (CHECKS WITH REC.) OBT

NO OTHER OBT'S FOUND

18" NOW ROTTED TO GROUND D, FIR AND ROOT HOLE
AT REC "S62°W, 36.2 FT" (CHECKS WITH REC) 1958

10" NOW 22" DIA MADRONE WITH A FULLY HEALED BLAZE
BEARS N25°E, 54.7 FT (CHECKS WITH REC) 1958

RENEWAL

Monument Set (Procedure and Description)

NONE


Monument Detail

N/A

New Accessories

TRUNKED MADRONE BARK SCRIBED CS T27SR7W
 529 BT" ON 8" DIA WESTERN TRUNK, BEARING AND DISTANCE
 TAKEN TO ROOT CROWN OF WESTERN TRUNK BEARS
 S75°E, 10.0 FT
 19" DIA MADRONE DOUBLE BLAZED AND SCRIBED "T27SR7W
 S 30 CS BT BEAR S 563 1/2 W, 50.3 FT

Sketch of Monument, Accessories, and General Area



Location & Comments

Comp. Declin. 17 3/4 °E
 Agency DCSO
 Party Chief RANDALL W. SMITH
 Notekeeper [Signature]
 Witnesses STEPHEN J. HAUSE

Address

Surveyor's Seal
 REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

OREGON
 JULY 25, 1990
 RANDALL W. SMITH
 2469