

GOVERNMENT CORNER RESTORATION FORM

Date: 11-3-1999 By: JC

This survey consists of:

Township 28S Range 7W Sec. 31

County DOUGLAS Map:

State OR Date 7-14-99

No. 100100.017 Narrative:

Corner Designation

Corner Rpt: 66/12-22A

531
56

DOUGLAS COUNTY

Condition Report Only

Not Found

Renewed

Unrecorded

Surveyed In

Referenced Out

Previous Renewals 1922 M-2, 1924 GLO, 1961 DCSO

Monument(s) Found: (Condition and Source)

2 1/2" BRASS CAP ON A 1 1/2" O.D. ~~BY 36" LONG IRON PIPE IS FOUND OUT~~
OF POSITION ON TOP OF GROUND.
1961

1 1/2" O.D. IRON PIPE. FLUSH
WITH GROUND. 1922?

3/4" GLO BRASS CAP ON A
3" O.D. 36" LONG IRON
PIPE OUT OF POSITION ON
TOP OF GROUND 1924

Accessories Found:

6" NOW 12" DIA PISTOL BUTT CEDAR WITH A
FULLY HEALED DOUBLY BLACK CENTER OF ANNA'S
TRUNK BEARS N 77 1/2 E 22.8 FT (REC. N 31 1/2 E,
22.7 FT AND 21.5 FT) 1961

12" NOW 24" DIA. 2 FT HIGH D. FIR STUMP WITH
A FULLY HEALED BLAZE. GOOD SCRIBING FOUND.
BEARS S 79 1/2 E, 63.6 FT (REC. S 78 1/2 E, 59.7 FT) GOES TO
A 1961 ALSO CORNER POSITION THAT WAS PROBABLY SET
IN ERROR) 1961

6" NOW 22" DIA 2 FT HIGH CEDAR STUMP, GOOD
SCRIBING FOUND, BEARS N 13 1/2 E 105.5 FT
(REC. N 31 1/2 E, 82.7 FT GOES TO A 1961 ALSO CORNER
POSITION THAT WAS PROBABLY SET IN ERROR.) 1961

NO MARKS FROM 1924 FOUND

COUNTY SURVEYOR OFFICE
T28S R7W

531
56

T29S
1961

U.S. GENERAL LAND

T28S
R7W
531

56
T29S
1924

OFFICE SURVEY

RENEWAL

Monument Detail

Monument Set (Procedure and Description)

RESET 1961 DCSO BC/IP AT A POSITION DETERMINED BY TIPS TO GLO BC/IP TO THE WEST AND M71-8 I.R. NORTHERLY. BRASS CAP STAMPED "RESET 1999".

NOTE RUSTY DIRT FOUND WHEN BC/IP RESET.


1924 GLO BC/IP (TR63 AP4 AP1 TR47) DCSO RESET/1999, BEARS S 88 3/4° E, 65.3 FT (AGREES WELL WITH 1924 REC.)

COUNTY SURVEYOR OFFICE
T285 R7W
RESET | 531
1999 | 56
T295
1961

New Accessories

- 1 1/2" O.D. IRON PIPE FLUSH WITH GROUND BEARS N 82° W, 10.8 FT. FROM M1-2
- 5/8" I.R. BEARS N 17 1/2° E, 226.5 FT. (AGREES WITH CALC. REC) M71-8
- 1924 GLO BC/IP (TR63 AP3, TR47 AP2) BEARS N 88 3/4° W, 96.4 FT. (AGREES WELL WITH 1924 REC.)
- 9" DIA MADRONE DOUBLE BLAZED AND SCRIBED "XCS BT" BEARS N 84 1/2° W, 36.7 FT

Sketch of Monument, Accessories, and General Area



Location & Comments

AREAS AROUND CORNERS APPEAR TO HAVE BEEN BURNED SEVERAL TIMES IN PAST

Comp. Declin. 17 3/4 W
Agency DCSO
Party Chief RANDALL W. SMITH
Notekeeper
Witnesses STEPHEN J. FLANK

Address

Surveyor's Seal

REGISTERED PROFESSIONAL LAND SURVEYOR

RANDALL W. SMITH

OREGON JULY 25, 1990 2489

