

RENEWAL

Monument Set (Procedure and Description)

Monument Detail

SURVEYED IN. SEE MAP
 M148-67 COUNTY SURVEYOR RECORDS

SET 5/8" X 60" I.R. W/ 1/2" DIA. ALUM
 CAP MARKED "DOUGLAS CO. SURVEYOR
 CS 1/16 S 19 2005"
 IRON ROD/ALUM CAP PROJECTS
 14" ABOVE GROUND.

A "NEARBY SURVEY MARKER" SIGN ON
 STEEL POST BEARS SOUTH, 25 FT.


(SEE OTHER SIDE)

New Accessories

37" DIA. X 3 FT. TALL SPRUCE STUMP WITH BOAT SPIKE MKD. "B.O.1"
 DRIVEN INTO TOP OF STUMP OVER CENTER OF ROOT CROWN.
 BOAT SPIKE BEARS S 69 1/4° W, 33.6 FT.

19" DIA. SPRUCE, DOUBLE BLAZED & SCRIBED "CS 1/16 S 19 CS BT"
 BEARS S 13 1/4° E, 10.7 FT.

Sketch of Monument, Accessories, and General Area



Location & Comments

CORNER LIES ON STEEP
 NORTHWEST FACING SLOPE
 IN CLEARCUT AREA W/ YOUNG
 SPRUCE TREES ESTABLISHED
 APPROX 75 FT FROM RIDGETOP.

GPS FILE = C091213A

Comp. Declin. 16 3/4° E

Agency D. C. S. O.

Party Chief S. FLAUSE

Notekeeper J. PIKE

Witnesses

Address

Surveyor's Seal

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

Randall W. Smith
 EXPIRES 6-30-2006

OREGON
 JULY 25, 1990
 RANDALL W. SMITH
 2489