

GOVERNMENT CORNER RESTORATION FORM

FILED

Date: 4/6/07 By: JC

Township 23 S Range 5W Sec. 36 County DOUGLAS

This survey consists of: _____
Map: _____

State OR Date 4-2-2007 No. 700100

Narrative: _____

Corner Rpt: 67/21-22

Corner Designation

TOWNSHIP CORNER
SE COR. SEC. 36

DOUGLAS COUNTY
SURVEYOR


- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewals 1981

MONUMENT DETAIL

Monument(s) Found: (Condition and Source)

2 1/2" DIA BRASS CAP, PROPERLY MARKED, 1" BELOW SURFACE OF GROUND



Accessories Found:

- 14" NOW 26" DIA. W. FIR, HEALED SINGLE BLAZE VISIBLE BEARS N 16° W, 68.7 FT. (AGREES W/REC.) 1981 B.T.
- 5/8" DIA. IRON ROD, BEARS S 45° E, 20.0 FT. (AGREES W/REC.) 1981
- 5/8" DIA. IRON ROD, BEARS S 45° W, 20.0 FT. (AGREES W/REC.) 1981
- 26" ALDER NOW GONE (REC. N 30° E, 75.3 FT.)

NOTE: AT REQUEST OF PROPERTY OWNER THE TWO 5/8" IRON RODS WERE REMOVED SO GROUND COULD BE PLOWED EASILY

C.S. File No 67/21-22

