

GOVERNMENT CORNER RESTORATION FORM

FILED

TOWNSHIP 30S RANGE 08W SEC. 9 PLSS # 400500

Date: 6/25/2013 By: X

This survey consists of:

DOUGLAS COUNTY OREGON

DATE JUNE 11, 2013

Map: \_\_\_\_\_

Narrative: \_\_\_\_\_

Corner Rpt: CS 67/38-32

Corner Designation

DOUGLAS COUNTY SURVEYOR

S9 | S10  
S16 | S15

Previous Renewals 1958, 2013  
Monument(s) Found: \_\_\_\_\_ (Condition and Source)

- \_\_\_\_\_ Condition Report
- \_\_\_\_\_ Not Found
- Renewed
- \_\_\_\_\_ Unrecorded
- \_\_\_\_\_ Surveyed In
- \_\_\_\_\_ Referenced Out

A 2 1/2 INCH DIAM. BRASS CAP (MARKED AS AT RIGHT) ON A 1 INCH I.D. IRON PIPE IS SOMEWHAT LOOSELY SET PROTRUDING APPROX 1 1/2 FEET FROM GROUND BUT WITH TOP SHARPLY BENT AND LEANING APPROX. 0<sup>o</sup> FEET SOUTHWESTERLY FROM PLUMB.

MONUMENT DETAIL

COUNTY SURVEYORS OFFICE  
T30S RBW

S9 | S10  
S16 | S15

Accessories Found

EVIDENCE OF 4 O.B.T.'S FOUND

A FIR, 15" DIA. NOW 34 INCH DIAMETER, 1 1/2 FOOT TALL SAWN FIR STUMP WITH POSSIBLE BUBLED BLAZE EDGE (NO SCRIBING REMAINS); BEARS N28°E, 16<sup>o</sup> FEET DISTANT (RECORD N28°E, 15<sup>o</sup> FT. IS A REASONABLE FACE MEASUREMENT)

A FIR, 16" DIA. NOW 34 INCH DIAM., 5 FOOT TALL FIR STUMP FALLEN AND OUT OF POSITION (DID NOT EXAMINE FOR BARK SCRIBING). A VERY LARGE AND INDISTINCT ROOT-HOLE IS NEAR THE RECORD BEARING AND DISTANCE.

A FIR, 46" DIA. NOW A LARGE BUT DISTINCT ROOT-HOLE WITH ROTTED FIR ROOT FRAGMENTS; BEARS S36°W, 35<sup>o</sup> FEET DISTANCE (AS PER RECORD).

A CEDAR, 16" DIA. NOW A LARGE INDISTINCT ROOT-HOLE WITH ROTTED CEDAR ROOT FRAGMENTS AGREES REASONABLY WITH RECORD B AND D.

EVIDENCE OF THREE 1958 RENEWAL B.T.'S.

A 10" W. FIR NOW A VERY INDISTINCT ROOT-HOLE NEAR RECORD B, AND D.

A 10" R. FIR NOW A 22 INCH DIAM. WHITE FIR NO LONGER SHOWING BLAZE EVIDENCE; BEARS S19 1/2°E, 49<sup>o</sup> FEET DISTANT (RECORD S18 1/2°E, 49<sup>o</sup> FT.).

AN 8" R. FIR NOW AN 18 INCH DIAM, 1 1/2 FOOT TALL SAWN FIR STUMP WITH EVIDENCE OF A LOW BLAZE (WE OPEN AND FIND SCRIBING "BT"); BEARS N12°E, 32<sup>o</sup> FEET DISTANT (RECORD N13°E, 32<sup>o</sup> FT.).

EVIDENCE OF THREE 2013 RENEWAL B.T.'S. A 16" W. FIR NOW A 16 INCH DIAM. WHITE FIR SCRIBED "S9 T30S RBW BT" ON A SINGLE BLAZE; BEARS N11°W, 9<sup>o</sup> FEET DISTANT (RECORD N9°W, 9<sup>o</sup> FT.).

A 12" W. FIR NOW A 12 INCH DIAM. DOUGLAS FIR SCRIBED "S16 T30S RB BT" ON A SINGLE BLAZE ("W" MISSING); BEARS S66 1/2°W, 30<sup>o</sup> FEET DISTANT (RECORD S68°W, 30<sup>o</sup> FT.).

A 10" W. FIR NOW A 10 INCH DIAM. DOUGLAS FIR SCRIBED "S15 T30S RBW BT" ON A SINGLE BLAZE; BEARS S77 1/2°E, 20<sup>o</sup> FEET DISTANT (RECORD S74°E, 20<sup>o</sup> FT.).

C.S. File CS 67/38-32

Monument Set (Procedure and Description)

MONUMENT DETAIL

WE REFERENCE PLUMB POSITION OF FOUND B.C. MONUMENT AND REMOVE FROM GROUND. PIPE IS STRAIGHTEND AND B.C. MONUMENT IS RETURNED TO REFERENCE PLUMB POSITION. MONUMENT IS NOW FIRMLY AND PLUMBLY SET PROTRUDING 4 INCHES ABOVE GROUND.

N/A


New Accessories

B.T. TAGS ARE CORRECTED OR ADDED AS NEEDED. MONUMENT AND TREES ARE FLAGGED.

Sketch of Monument, Accessories, and General Area

Location & Comments

(SKETCH SHOWS INTACT B.T.S AND STUMPS)



AT TOP OF LOW RIDGE (AS DESCRIBED) IN REPROD FOREST OF W. FIR, D. FIR AND SOME CEDAR.

Comp. Decline. 15 1/2° E

Agency D.C.S.O.

Party Chief STEPHEN JOHN FLAUSE

Note keeper Stephen John Flause

Witnesses MIKE S. KOCH

Surveyor's Seal

REGISTERED PROFESSIONAL LAND SURVEYOR

*Randall W. Smith*

OREGON JULY 25, 1990 RANDALL W. SMITH 2400

RENEWAL - 6-30-14