

GOVERNMENT CORNER RESTORATION FORM

FILED

TOWNSHIP 23S RANGE 07W SEC. 33 PLSS # 340100

Date: 9-15-2014 By: X
This survey consists of:

DOUGLAS COUNTY OREGON

DATE AUG. 12, 2014

Map: _____

Narrative: _____

Corner Rpt: Cs 67/4-4L

Corner Designation

DOUGLAS COUNTY
SURVEYOR

1/4 33 ONLY

- Condition Report
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewals RESUREY REESTA. 1976
Monument(s) Found: (Condition and Source)

MONUMENT DETAIL

FROM THE 1976 PROPORTIONED REESTABLISHMENT, A 5/8 INCH DIAMETER IRON ROD (REBAR) JUST BELOW GROUND SURFACE. IRON ROD LEANS S77°W, 0 1/2 FEET OFF OF PLUMB BUT GROUND CONDITIONS AND STRAIGHTNESS OF ROD INDICATE IT WAS ORIGINALLY SET AS FOUND.

N/A

Accessories Found

BEARINGS AND DISTANCES MEASURED FROM TOP OF IRON ROD AS FOUND.

NO EVIDENCE OF ORIGINAL BEARING TREES.

EVIDENCE OF THE TWO 1976 BEARING TREES.

A 24" FIR NOW A SAWN, ROTTED, 26 INCH DIAM. 2 FOOT TALL FIR STUMP WITH HEALED BLAZE EVIDENT (BLAZE OPENED TO FIND SCIBING "1/4 S33 BT" AS PER RECORD). THIS STUMP BEARS N56°W, 23 1/2 FEET DISTANT (RECORD N52°50'W, 22 3/4 FEET, A FACE DISTANCE).

A 28" FIR NOW A BROKEN AND ROTTED 22 INCH DIAM. 2 FOOT TALL FIR STUMP WITH POSSIBLE BLAZE EVIDENCE IN BARK BUT WITH ALL BLAZE AND FACE EVIDENCE ROTTED AWAY. THIS STUMP BEARS N34°E, 34 1/2 FEET DISTANT (RECORD N32°14'E, 35 1/2 FEET, A POSSIBLE SLOPE DIST.).

N/A

N/A

New Accessories

FOUR NEW BEARING TREES:

A 20 INCH DIAM. DOUGLAS FIR SCRIBED "1/4 S33CS" "BT" ON A DOUBLE BLAZE; BEARS N43 1/2° E, 12 3/4 FEET DISTANT.


AN 8 INCH DIAM. DOUGLAS FIR SCRIBED "1/4 S33" "CSBT" ON A DOUBLE BLAZE; BEARS N84° E, 21° FEET DISTANT.

A 20 INCH DIAM. GRAND FIR (TRUNK IS VERY CROOKED IN ITS FIRST 6 FEET) SCRIBED "1/4 S33CS" "BT" ON A DOUBLE BLAZE; BEARS N82° W, 58 1/2 FEET DISTANT.

A 9 INCH DIAM. DOUGLAS FIR SCRIBED "1/4 S33CS" "BT" ON A DOUBLE BLAZE; BEARS N38 1/4° W, 62 3/4 FEET DISTANT.

Sketch of Monument, Accessories, and General Area

Location & Comments



MONUMENT IS IN VERY OLD MIXED
FIR REPROD. FOREST AND ON NORTH
EDGE OF OLD CATROAD.

Comp. Decline. 15 1/2° E
Agency N.C.S.D.
Party Chief STEPHEN JOHN FLAISE
Note keeper Stephen John Flaiss
Witnesses MIKE S. KOCH

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Randall W. Smith

OREGON
JULY 25, 1990
RANDALL W. SMITH
2400

RENEWAL 6-30-2016