

GOVERNMENT CORNER RESTORATION FORM

FILED

TOWNSHIP 24S RANGE 04W SEC. 20 PLSS # 047030

Date: 11-24-2015 By: JC

DOUGLAS COUNTY OREGON

DATE FEB. 10, 2015

This survey consists of:

Map: \_\_\_\_\_

Narrative: \_\_\_\_\_

Corner Rpt: CS 67/42-10

Corner Designation

DOUGLAS COUNTY SURVEYOR

SW  
DLC 47

- Condition Report
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewals 1963  
Monument (s) Found: \_\_\_\_\_ (Condition and Source)

FROM THE 1963 RENEWAL A 2 1/2 INCH DIAMETER BRASS CAP (MARKED AS AT RIGHT) ON A 1 INCH I.D. IRON PIPE IS FIRMLY SET PROTRUDING 12 INCHES ABOVE GROUND.

AN OLD IRON GATE HINGE, AS DESCRIBED IN 1963 RENEWAL, IS FOUND FLUSH WITH GROUND ON NORTH EDGE OF BC MONUMENT.

FENCE CORNER WITH FENCES RUNNING NORTH, SOUTH AND EAST IS NORTH 10 FEET FROM B.C. (RECORD NORTH 9 E FEET).

MONUMENT DETAIL

COUNTY SURVEYORS OFFICE

T 24S

SW  
DLC  
47

R 4W

1963

Accessories Found

TWO DBT'S FOUND IN 1963 NOW FALL IN A VINEYARD CLEARING AND NO EVIDENCE REMAINS.

THE 1963 RENEWAL BEARING TREE AN 18" W. OAK NOW A 31 INCH DIAMETER WHITE OAK WITH A FULLY HEALED SINGLE BLAZE; BEARS N 89° E, 24.5 ± FEET DISTANT (AS PER RECORD).

C.S. File 67/42-10

RENEWAL

Monument Set (Procedure and Description)

MONUMENT DETAIL

N/A

N/A

New Accessories

A 17 INCH DIAM. DOUGLAS FIR SCRIBED "SWDLC 47 CS" "BT" ON A DOUBLE BLAZE; BEARS S65 1/2° E, 82 1/2 FEET DISTANT.


A DOUBLE-TRUNK DOUGLAS FIR THE NORTHERLY 21 INCH DIAM. TRUNK OF WHICH IS SCRIBED "SWDLC 47" "CSBT" ON A DOUBLE BLAZE. THE C.R.C. OF THIS TREE BEARS S22 1/2° E, 50 1/2 FEET DISTANT.

A DOUBLE-TRUNK WHITE OAK (GROWING AGAINST AN E-W FENCE) THE SOUTHERLY 10 INCH DIAM. TRUNK OF WHICH IS SCRIBED "CSBT" ON A HIGH BLAZE (4 1/2" ABOVE GROUND). THE C.R.C. OF THIS TREE BEARS N41° E, 13 1/2 FEET DISTANT.

C.R.C. = Center Root Collar

Sketch of Monument, Accessories, and General Area

Location & Comments



MONUMENT IS NEAR TOP OF 13 ROAD EAST-WEST RUNNING RIDGE - VINEYARD TO WEST. BRUSH OVERGROWN PASTURE IN NE QUADRANT. FIR, PINE AND OAK WOODS IN SE QUADRANT.

Comp. Decline. 15 1/4° E  
Agency DCSO  
Party Chief STEPHEN JOHN FLAUSE  
Note keeper Stephen John Flauser  
Witnesses MIKE S. KOCH

Surveyor's Seal  
REGISTERED PROFESSIONAL LAND SURVEYOR  
*Kristian O. DeGroot*  
OREGON  
JULY 17, 1981  
KRISTIAN O. DeGROOT  
# 1941

RENEWAL 12/31/15