

**GOVERNMENT CORNER RESTORATION FORM  
DOUGLAS COUNTY SURVEYOR**

TOWNSHIP 29S RANGE 03W SECTION 1 & 2

PLSS/GCDB No. 29-03-600700

CORNER DESIGNATION: Witness Corner S2/S1

CORNER HISTORY, PREVIOUS RENEWALS OR SURVEYS:


- See DCSO survey and renewal records for PLSS: 29-03-600700.

FILED
Date: <u>12-5-18</u>
By: <u>JC</u>
Corner Form: <u>CS67/45-23</u>
Field Notes: _____
DOUGLAS COUNTY SURVEYOR
DATE: October, 08, 2018
<input type="checkbox"/> Condition Report Only
<input type="checkbox"/> Not Found
<input checked="" type="checkbox"/> Renewed
<input type="checkbox"/> Unrecorded
<input type="checkbox"/> Surveyed In
<input type="checkbox"/> Referenced Out

**MONUMENT DETAIL**

MONUMENT FOUND (CONDITION AND SOURCE):

- A 2" i.d. iron pipe by James J. Carlson, USBLM Cadastral Surveyor, in 1976, firmly set, projecting 4" above ground in a 18" diam. stone collar with a 3 1/4" diam. brass cap marked as follows:
- The monument is a Witness Corner, the true corner position bears N.89°29'W., 0.70 Chains per a 1976 USBLM Dependent Resurvey.



ACCESSORIES (CONDITION, SOURCE & RECORD):

Bearing Trees by Carlson 1976:

- A 18" diam. D. Fir bears S 17° E, 30.7 ft. with healed double blaze.
- A 16" diam. Alder bears S 25° W, 128.6 ft. with healed double blaze (Rec. 196.5 lks. = 129.7 ft.)

New Bearing Trees:

- A 14" D. Fir bears S 54° W, 21.9 ft. scribed "T29S R3W S2", "CS BT" on a double blaze .

LOCATION & COMMENTS:

The corner falls in South Myrtle Creek. The witness Corner is South 20 ft from the center of the creek. All new bearing trees are double blazed and tagged. No trees were marked to the North due to the creek and thick riparian zone.

N 526,770.79

E 4,247,964.91

GEODETIC COORDINATES  
LATITUDE: 43°05'03.383"N.  
LONGITUDE: 123°01'15.117"W.  
ELLIPSOID HEIGHT:  
DATUM: NAD 83, Epoch 2010.00  
SOURCE: Trimble GeoXT 6000

COMPASS DECLINATION: 15° E.  
AGENCY: DCSO  
PARTY CHIEF: S. J. FLAUSE  
WITNESSES: JEFF A. LORSUNG  
NOTES: ATTACHED

C100811A

CS67/45-23

REGISTERED PROFESSIONAL LAND SURVEYOR  <i>Kristian O. Degroot</i> OREGON JULY 17, 1981 KRISTIAN O. DEGROOT 1941 RENEWAL DATE: 12-31-2019
---

PBS

2903600700

~~10-8-2018~~  
10-8-2018  
from Creek

46.2

CARLSON 1978 TREES

- 5" Fir, S 17° E, 3069
- 10" ALDER, S 25° W, 12969

5" Fir NOW 18" FIR, S 17° E, 3069

10" → 16" ALDER, S 25° W, 1286

NEW BT:

14" D FIR, "T29SR3WS2", "CSBT"  
S 54° W 219

NO GOOD TREES TO THE NORTH  
(IN RIPARIAN ZONE OF CREEK)

CENTER CREEK LIES 20° FT  
NORTH

3 1/4" BRASS DEPT OF INTERIOR CAP  
PROJECTING 4" IN STONE COLLAR.

CS 67/45-23

