

GOVERNMENT CORNER RESTORATION FORM

FILED

TOWNSHIP 24S RANGE 1W SEC. 29 PLSS # 200240

Date: 8/2/2023 By: SC

This survey consists of:

Map: _____

Narrative: _____

Corner Rpt: CS 67/56-50

DOUGLAS COUNTY OREGON

DATE 7-24-23

DOUGLAS COUNTY SURVEYOR

Corner Designation

1/4 cor 30/29

Monument(s) Found: (Condition and Source)

2 1/2" County Surveyors
BRASS CAP up 8"

___ Condition report

___ Not Found

Renewed

___ Unrecorded

___ Surveyed In

Previous Renewals

DCSO 1966 CS 52/42-51
DCSO 1970 CS 54/27-184
DCSO 1973 CS 56/34-6 pg 2

MONUMENT DETAIL

County Surveyors
OFFICE
T 24S R1W
1/4 530/529
1966

Accessories Found

32" X 7 FT Broken - Shattered Fir Stump
N38°E 17.8 FT
Rotted To Ground Fir Stump N26°W
9.2 FT

C.S. File 67/56-50

New Accessories

23" X 2 1/2' FT Red Cedar Stump N180°E
6.8 FT 3 1/2" MAG NAIL TOP CENTER

6" X 8" X 3' TALL Steel Gate Latch Post
S 85 1/2° W 73.6 FT

6" X 8" X 9' TALL Gate Hinge Post S 79° W
69.1 FT

Sketch of Monument, Accessories, and General Area

Location & Comments

CORNER ON N. EDGE OF
EAST - WEST RIDGE IN
OLDER D. FIR REPROD


Cor 20' N. OF Gravel
ROAD RUNNING
West

AREA BURNED
9/2020

OCRS COORDINATE SYSTEM
COTTAGE GROVE - CANYONVILLE
ZONE

Comp. Decline. 14 1/2° E
Agency DCSD
Party Chief S. FIAUSE
Note keeper
Witnesses J. Korsung

N 228551.688
E 295046.920



EXPIRES: 12/31/2024

2/3 CS67/56-50

MM GPS 7/24/23
TIME - 11:44
H.I. - 2.000M

RENEWED 7/24/23

TOWNSHIP 24 RANGE 01 POINT IDENTIFIER # 200240

PRIMARY CORNER DESCRIPTION 1/4 Cor. Secs. 29 & 30

Alias _____ Description _____
Alias _____ Description DCRS CANYONVILLE COTTAGE GROVE COORDS
Alias _____ Description _____
Alias _____ Description 228.551.683 N
295046.920 E

GLO survey by Carl S. Nicklin, Dep. Surveyor under contract # 664, dated May 23, 1896 - (DCSO recs Vol. 7 Page(s) 2844)

Set a cedar post, 3 1/2 ft. long, 3" sq., 24" in the ground, for 1/4 sec. cor. marked 1/4 S on W face, from which
A fir, 30" dia., bears N.38°E., 27 lks., mkd: 1/4 S BT.
A fir, 15" dia., bears N.36°W., 14 lks., mkd: 1/4 S BT.
This cor. is on top of spur, sloping W about 75 ft. above creek, last noted.

Douglas Co. Surveyors Office - Vernon R. Tracy & Crew - Nov. 1966 - C.S. File 52/42-51

32" x 7 FT
BROKEN

Found - Orig. ~~30"~~ now 48" Fir, N.38°E., 17.8 ft., alive, shows good scar.
~~OFF SHATTERED STUMP~~
~~ROTATED TO GROUND~~ Orig. 15" now 28" Fir, N.36°W., 9.2 ft., alive open & find "1/4" scribe.

Set - Brass cap at cor. mkd: COUNTY SURVEYORS T24S R1W OFFICE 1966 1/4 S 30 | S 29

MM GPS
43.45926
122.84009

New BTs - 15" I Cedar N 59°W., 14.2 ft., mkd: 1/4 S20 CS BT.
14" D. Fir N.45°E., 23.6 ft., mkd: 1/4 S29 CS BT.
Note: This corner lies on top of ridge, sloping West.

Fd. Ok by VRT, DCSO May 1970 - C.S. File 54/27-184
Fd. OK by VRT, DCSO July 25, 1973 - C.S. File 56/34-6 Pg2
DECLINATION 14 1/2° E

NEW REFS

23" x 2 1/2 FT TALL RED CEDAR STUMP WITH 3 1/2" MAGNAIL TOP CNTR. N 80° E, 68 FT.

6" x 8" x 3 FT TALL STEEL GATE LATCH POST; BEARS S 85 1/2° W, 73 1/2 FT

6" x 8" x 9 FT. TALL STEEL GATE HINGE POST; BEARS S 79° W 69 1/2 FT

MONUMENT ON NORTH EDGE OF EAST - WEST RUNNING RIDGE
20 FT. NORTH FROM Q OF WEST RUNNING GRAVEL SPUR RD.
AREA IS IN OLDER D. FIR REPROD.