

GOVERNMENT CORNER RESTORATION FORM

FILED

TOWNSHIP 26S RANGE 2W SEC. 8

PLSS # 240520

Date: 8/3/2023 By: E
This survey consists of:

DOUGLAS COUNTY OREGON

DATE 8-21-23

Map: _____

Narrative: _____

Corner Rpt: CS 67/56-57

Corner Designation

S.E. 1/4 S 8

DOUGLAS COUNTY
SURVEYOR

Monument(s) Found: (Condition and Source)

1" Iron pipe up 7"
LEADS slightly SSW

___ Condition report

___ Not Found

Renewed

___ Unrecorded

___ Surveyed In

Previous Renewals

Ramsey CS 51/86
Hoffine 2016 M172-7

MONUMENT DETAIL

Accessories Found

BURNED - SAWN 27" X 3 FT D. FIR STUMP
N 5 1/4° W 27.7 FT (REC 27.5 FT) FULLY HEALED
SINGLE BLAZE ADD 3 1/2" MAG NAIL TOP
CENTER

BURNED - DEAD 9" D. FIR N 52 1/2° W 15.6 FT
(REC 15.5 FT) PARTLY HEALED SINGLE BLAZE
SOME SCRIBING VISIBLE ADD 3 1/2" MAG
NAIL RIGHT SIDE CENTER

C.S. File 67/56-57

New Accessories

24" X 4 FT BURNED - SAWN FIR STUMP
N 31° W 5.2 FT 3 1/2" MAG NAIL TOP
Center

Sketch of Monument, Accessories, and General Area

Location & Comments


BCRS Coordinate System
Cottage Grove - Canyonville
Zone

N 176489.519
E 264358.986

MON 30 FT WEST
OF RIDGE SPIKE
AND 10' LOWER

ARE BURNED
9/2020

Comp. Decline. 14 1/2° E
Agency DCSO
Party Chief S. F. AUSE
Note keeper
Witnesses J. LORSUNG



EXPIRES: 12/31/2024

CORNER INFORMATION:

1) THE QUARTER CORNER BETWEEN SECTIONS 8 AND 9 Gcdb 300540
FOUND 1959 BLM BRASS CAP 0.8 FEET ABOVE GROUND
- 12" DOUGLAS FIR BEARS N77°E 17.9 FEET (RECORD N75°E 19.14 FEET) HEALED FACE AND BLM TAG
- 26" DOUGLAS FIR BEARS N68 1/4°W 29.9 FEET (RECORD N70°W 29.37 FEET) HEALED FACE AND BLM TAG
CORNER LIES ON NORTH FACING SLOPE IN MOUND OF STONES

2) THE SOUTH 1/16TH CORNER BETWEEN SECTIONS 8 AND 9 Gcdb 300520
FOUND 1959 BLM BRASS CAP 0.2 FEET ABOVE GROUND
- 25" DOUGLAS FIR BEARS S60 1/2°E 21.4 FEET (RECORD S61 1/2°E 21.78 FEET) HEALED FACE AND TAG
- 12" FIR SNAG BEARS S62 1/2°W 5.6 FEET (RECORD S58 1/2°W 5.61 FEET) HEALED FACE AND BLM TAG
- 8" DOUGLAS FIR BEARS S71 1/2°W 25.2 FEET WE SCRIBE S 1/16 S8 BT AND TAG TREE
CORNER LIES ON SOUTHEAST SLOPE WITH LARGE BLM TIMBER TO EAST.

3) THE SOUTHEAST SECTION CORNER FOR SECTION 8 Gcdb 300500
FOUND 1918 USGLO BRASS CAP 1.0 FEET ABOVE GROUND
- 67" DOUGLAS FIR BEARS N41°E 19.4 FEET (RECORD N40°E 18.48 FEET) HEALED FACE AND BLM TAG
- 38" DOUGLAS FIR BEARS S20 1/4°E 7.7 FEET (RECORD S20°E 6.8 FEET) HEALED FACE AND BLM TAG
- 53" DOUGLAS FIR BEARS S54°W 25.4 FEET (RECORD S55°W 25.74 FEET) HEALED FACE AND BLM TAG
- 14" CHINQUAPIN BEARS N74 1/4°W 10.55 FEET (RECORD N75 1/4°W 10.56 FEET) HEALED FACE AND BLM TAG
CORNER LIES ON EAST FACING SLOPE IN HEAVY HUCKLEBERRY BRUSH

4) THE EAST 1/16 TH CORNER BETWEEN SECTIONS 8 AND 17 Gcdb 260500
FOUND 1959 BLM BRASS CAP 0.3 FEET ABOVE GROUND
- 40" DOUGLAS FIR BEARS S52°E 86.4 FEET (RECORD S51 1/4°E 87.12 FEET) HEALED FACE AND BLM TAG
- ROTTEN FIR STUMP BEARS N84°E 49.7 FEET (RECORD N84 1/2°E 50.16 FEET) NO VISIBLE MARKS
- 13" DOUGLAS FIR BEARS N72 1/2°E 16.3 FEET WE SCRIBE E1/16 S8 BT AND TAG TREE
CORNER LIES ON SOUTHWEST SLOPE APPROX. 75 FEET WEST OF ROAD

5) THE QUARTER CORNER BETWEEN SECTIONS 8 AND 17 Gcdb 240500
FOUND 1959 BLM BRASS CAP 0.4 FEET ABOVE GROUND
- 20" DOUGLAS FIR BEARS S41 1/4°E 22.11 FEET (RECORD S41°E 22.44 FEET) HEALED FACE AND BLM TAG
- 28" DOUGLAS FIR BEARS N57°W 10.3 FEET (RECORD N53 1/2°W 11.22 FEET) HEALED FACE AND BLM TAG
CORNER LIES ON STEEP SOUTH FACING SLOPE APPROX. 100 FEET SOUTH OF OLD ROADWAY

6) THE CENTER SOUTH 1/16 TH CORNER FOR SECTION 8 Gcdb 240520
FOUND 1" IRON PIPE 0.2 FEET ABOVE GROUND PER SURVEY CS 51/86
- ROTTEN FIR STUMP BEARS N10 1/4°W 19.6 FEET (RECORD N10°W 19.8 FEET) VISIBLE SCRIBING
- ROTTEN FIR STUMP BEARS S79 1/4°W 5.9 FEET (RECORD S70°W 5.28 FEET) VISIBLE SCRIBING
- 9" DOUGLAS FIR BEARS N23 3/4°W 11.8 FEET WE SCRIBE CS 1/16 S8 BT AND TAGGED TREE
- 15" DOUGLAS FIR BEARS N49°E 23.5 FEET WE SCRIBE CS 1/16 S8 BT AND TAGGED TREE
CORNER LIES ON STEEP WEST FACING SLOPE 27Z FT.

7) THE SOUTHEAST 1/16 TH CORNER FOR SECTION 8 Gcdb 260520
FOUND 1" IRON PIPE 0.6 FEET ABOVE GROUND PER SURVEY CS 51/86
- 26" DOUGLAS FIR BEARS N5 1/4°W 22.0 FEET (RECORD N5°W 27.06 FEET) HEALED FACE AND TAG
- 8" DOUGLAS FIR BEARS N52 1/2°W 15.5 FEET WE SCRIBE SE1/16 S8 BT AND TAG TREE
CORNER LIES ON WEST SIDE OF MAIN RIDGE 15Z FT.

8) THE CENTER WEST EAST SOUTHEAST 1/256 CORNER FOR SECTION 8
SET 5/8" X 40" IRON ROD WITH 2 1/2" ALUMINUM CAP MARKED LONE ROCK TIMBER S8 CW E SE 1/256 2016 PLS 2291
- 18" DOUGLAS FIR BEARS S23°W 16.2 FEET WE SCRIBE BT AND TAG TREE
- 17" DOUGLAS FIR BEARS N57 1/2°E 33.7 FEET WE SCRIBE BT AND TAG TREE
CORNER LIES ON SOUTHEAST SLOPE APPROX. 80 FEET S45°E FROM PROPOSED 2016 NEW ROAD CONSTRUCTION. WE PUT METAL U - POST 0.5 FEET NORTH OF CORNER.

9) THE CENTER WEST EAST EAST 1/256 CORNER FOR SECTION 8
SET 5/8" X 40" IRON ROD WITH 2 1/2" ALUMINUM CAP MARKED LONE ROCK TIMBER S8 CW E E 1/256 2016 PLS 2291
- 13" DOUGLAS FIR BEARS N81 1/4°E 8.4 FEET WE SCRIBE BT AND TAG TREE
- 15" DOUGLAS FIR BEARS S1 1/4°E 28.3 FEET WE SCRIBE BT AND TAG TREE
CORNER IS 0.2 FEET ABOVE GROUND ON SOUTH FACING SLOPE. WE PUT METAL U - POST APPROX. 0.5 FEET NORTH OF CORNER.

10) THE CENTER EAST 1/16 TH CORNER FOR SECTION 8 Gcdb 260540
SET 5/8" X 40" IRON ROD WITH 2 1/2" ALUMINUM CAP MARKED LONE ROCK TIMBER CE 1/16 S8 2016 PLS 2291
- 14" DOUGLAS FIR BEARS N8 1/4°E 9.3 FEET WE SCRIBE CE1/16 S8 BT AND TAG TREE
- 12" DOUGLAS FIR BEARS S11 1/2°W 39.0 FEET WE SCRIBE CE 1/16 S8 BT AND TAG TREE
FOUND RAMSEY BEARING TREE STUMPS WITH IRON PIPE PUSHED OUT OF POSITION. WE RESET CORNER AT PROPORTIONATE DISTANCE. CORNER LIES AT NORTH EDGE OF THREE WAY ROAD JUNCTION. WE SET CORNER 0.1 FEET BELOW THE ROAD SURFACE AND PUT A METAL U - POST APPROX. 5.0 FEET NORTH OF CORNER.

11) THE CENTER QUARTER CORNER FOR SECTION 8 Gcdb 240540
FOUND 1 1/2" IRON PIPE PER SURVEY CS 51/86
- 62" FIR STUMP BEARS N89 1/2°E 19.3 FEET (RECORD S88 °E 17.6 FEET) WEYCO TAG
- 30" FIR STUMP BEARS N61 1/2°E 24.1 FEET WEYCO TAG AND MAG NAIL TAG READS S60 1/2°W 26.3 FEET NO RECORD
- 12" DOUGLAS FIR BEARS N28 3/4°E 27.7 FEET WE SCRIBE C1/4 S8 BT AND TAG TREE
- 6" DOUGLAS FIR BEARS N80°W 13.7 FEET WE SCRIBE C1/4 S8 BT AND TAG TREE
- 13" DOUGLAS FIR BEARS N89 1/2°E 19.3 FEET WE SCRIBE C1/4 S8 BT AND TAG TREE
- 11" DOUGLAS FIR BEARS S31 1/4°W 34.4 FEET WE SCRIBE C1/4 S8 BT AND TAG TREE
CORNER LIES APPROX. 65 FEET WEST OF UNMAINTAINED ROCK ROAD

T265, R2W, 260520

RENEWED 8/21/23 DECLINATION 14 1/2°E

PIPE IS SOLID LEANS SLIGHTLY SSW, PROT 7"

BURNED SAWN 27" x 3" STUMP BURNED DEAD 9"

MON ~ 30 FT WEST OF RIDGE SPINE AND 10 FT LOWER

PHSB, ADD 3 1/2" MAG NAIL TOP CENTER PHSB PARTIAL SCRIBG VIS. ADD 3 1/2" MAG NAIL RSC NEW REF: 24" x 4 FT. BURNED SAWN FIR STUM WITH 3 1/2" MAG NAIL TOP CNT, BEARS N31°W, 52 FT.

OCCAS CANYONVILLE COTTAGE GROVE COURDS

176489.519 N 264358.986 E

LEGEND table with symbols for found brass caps, iron pipes, iron rods, and records from 1960 BLM plat 245.

REGISTERED PROFESSIONAL LAND SURVEYOR

Signature of Kim W. Hoffman

