

GOVERNMENT CORNER RESTORATION FORM

FILED

TOWNSHIP 23S RANGE 1W SEC. 30 PLSS # 700151

Date: 5/14/25 By: KL
This survey consists of:

DOUGLAS COUNTY OREGON

DATE 5/1/25

Map: _____
Narrative: _____
Corner Rpt: CS 67140-28

Corner Designation

1/4 531 only T23-1E

DOUGLAS COUNTY
SURVEYOR

Monument(s) Found: (Condition and Source)

1925 GLO BRASS CAP

- Condition report
- Not Found
- Renewed
- Unrecorded
- Surveyed In

Previous Renewals

DCSO 1976 CS 59/26-5

MONUMENT DETAIL

1/4 531
1925

Accessories Found

BURNED DEAD 26" FIR S 26° E 18.5 FT
Rehealed BLAZE ADD 3 1/2" MAG NAIL
RIGHT SIDE CENTER

BURNED DEAD 42" FIR N 52° E 39.0 FT
(REC N 50° E) Fully Healed SINGLE BLAZE
ADD 3 1/2" MAG NAIL RIGHT SIDE CENTER

BURNED DEAD 13" FIR S 61 1/2° E 17.0 FT
(REC S 63° E) Fully Healed DOUBLE BLAZE
ADD 3 1/2" MAG NAIL RIGHT SIDE CENTER

2 Step 1 P X C post with USFS
MONUMENT SIGNS North 1.5 FT and
EAST 13.0 FT

Monument Set (Procedure and Description)

MONUMENT DETAIL

New Accessories

BURNED DEAD Hemlock N 48° E 13.2 FT
with 3 1/2" MAG NAIL RIGHT SIDE Center

Sketch of Monument, Accessories, and General Area

Location & Comments


OCRS Coordinate System
Cottage Grove - Canyonville
Zone

MON IS 50' ± West
OF ROAD 2422Z

N 688003.211
E 4326865.319

Comp. Decline. 14 1/2° E
Agency DISO
Party Chief SI Fause
Note keeper
Witnesses J. Forslund

CS 67160-28 pg 2/3



EXPIRES: 12/31/2026

TOWNSHIP 23 RANGE 01 POINT IDENTIFIER # 700151

PRIMARY CORNER DESCRIPTION W. 1/4 Cor. for Sec. 31 only, T23-1E

Alias _____	Description _____
Alias _____	Description _____
Alias _____	Description _____
Alias _____	Description _____

OCS CANYONVILLE COTTAGE GROVE COORDS
688003.211 N (SIS MAP LOCATION IS BAD)
4326865.319 E

GLO survey by John G. Collins; Dan P. Mumbrue; Theodore Vander Meer; under special instructions, dated May 9, 1922 - (DCSO records Vol. 5 Page(s) 2164-65)

A point 40.00 chains southing from the point for the cor. of secs. 30 and 31 only, determined as hereinafter set forth. Set an Iron post 3 ft. long, 1" dia., 28" in the ground for 1/4 sec. cor. of sec. 31 only with brass cap mkd.

1/4 S 31
1925

from which

A Fir 12" dia., bears N.50°E., 54 lks. dist. mkd. 1/4 S31 BT.

A Fir 6" dia., bears S.26°E., 28 lks. dist. mkd. 1/4 S31 BT.

Douglas County Surveyors Office - Vic Cangie & Michael Tompkins - Nov. 2, 1976 - C.S. File 59/26-5

5/1/25

Found - 1925 GLO brass cap properly marked.
 6" now ~~15"~~ Fir bears S.26°E. 18.5 ft. We open and find scribing. Tree alive and well.
 12" now ~~34"~~ Fir bears N.50°E. 39 ft. (Rec. 35.6 ft.) Tree alive and well.

ADD 3 1/2" MAG NAIL RSC TO FOUND B.T.S
REHEALED BLAZING

At corner point, We reset iron pipe with brass cap uprooted at site. *NOW PROT. 9"*

New BT - An ~~8"~~ Fir bears S.63 1/2°E., 170 ft scribed 1/4 S31 CS BT with double blaze.
Corner is 50 ft. West of Road 2422 Z.

DECLINATION 14 1/4° E

ALSO FOUND A STEEL FNC. POST WITH USFS SURVEY MONUMENT SIGN NORTH, 15 FT

" " " " " " " " EAST, 13 FT

NEW REF.

BURNED DEAD HEMLOCK WITH 3 1/2" MAG NAIL RSC BEARS N48°E, 13 FT.

MINIGIS
43.53258
122.74144

BURNED DEAD 26"

BURNED DEAD 42"

BURNED DEAD 13"