

GOVERNMENT CORNER RESTORATION FORM

FILED.

TOWNSHIP 32S RANGE 9W SEC. 6 PLSS # 100600

Date: 6/11/25 By: Ke  
This survey consists of:

DOUGLAS COUNTY OREGON

DATE 5/28/25

Map: \_\_\_\_\_

Narrative: \_\_\_\_\_

Corner Rpt: 67/60-39

Corner Designation

DOUGLAS COUNTY  
SURVEYOR

56  
57

Monument(s) Found: (Condition and Source)

Condition report

2 1/2" GLD BRASS CAP

Not Found

Proj 12"

Renewed

Unrecorded

Previous Renewals

Surveyed In

DOSO 1967 CS 54/44-1

MONUMENT DETAIL

Accessories Found

32" D. FIR SWAG N184°E 21.9 FT (Rec  
22.4 FT) Fully Healed Single BLAZE

ADD 3 1/2" MAG NAIL Left Side Center

54" D. FIR SWAG S14°E 40.2 FT (Rec 38.9 FT)

FD Spike Nail Left Side Center

Illegible Scribes Visible on previously  
opened FACE

33" D. FIR S67°E 58.7 FT (Rec 57.0 E

59.6 FT) FD Spike Left Side Center

Fully Healed Double BLAZE

New Accessories

5/8" X 30" Iron Rod with DCSO yellow  
plastic cap proj 3" Bore N 59° W  
12.5 FT

Sketch of Monument, Accessories, and General Area

Location & Comments


MON IS ON steep SSW slope  
in old Growth Fir Forest  
OCRS coordinates  
Cottage Grove - Canyonville  
zone

MON IS APPROX  
150 FT WEST  
OF GRAVEL ROAD

N-7422.773  
E 35794.319

Comp. Decline. 14 1/2° E  
Agency DCSO  
Party Chief S. FIAUSE  
Note keeper  
Witnesses J. KORSUNG

CS 67/60-39 pg 2/3



EXPIRES: 12/31/2026

TOWNSHIP 32 RANGE 09 POINT IDENTIFIER # 100600

PRIMARY CORNER DESCRIPTION Sec. Cor. for 6 & 7 only (West)

Alias _____	Description _____
Alias _____	Description _____
Alias _____	Description _____
Alias _____	Description <u>OCRS CANYONVILLE COTTAGE GROVE COORD. S</u>

-7422.773N  
35794.319E

GLO Resurvey by Fred Mensch and Gerald A. Sorrels, Surveyors under Special Instructions, Group #35, dated Dec. 22, 1916 - (DCSO records Vol. 21 Page(s) 8873)

Set an iron post 3 ft. long, 2" dia., 24" in the ground, for cor. of secs. 6 and 7, with brass cap mkd.

T32S  
S6  
S7  
R9W

1917

from which

A Fir 30" dia., bears N.84°E., 34 lks. dist. mkd. T32S R9W S6 BT.

A Fir 48" dia., bears S.14°E., 59 lks. dist. mkd. T32S R9W S7 BT.

Douglas Co. Surveyors Office - John M. Powell, and crew June 1967 - C.S. File 54/44-1

2 1/2" GLO CAP AS ABOVE - PROT. 12"

Found - 1917 GLO brass cap, properly mkd 21 1/2 FT SET 3 1/2" MAG NAIL L.S.C. now 40" D. Fir N.84°E., 22 1/4 ft., shows good scar. FHSB

32" INTACT SNAG

54" INTACT SNAG

48" now 60" D. Fir S.14°E., 38 1/2 ft., opened and found scribing. FOUND SPIKE NAIL L.S.C. DIST. TO NAIL

New BT - 48" D. Fir S.76°E., 59 6 ft. mkd. T32S R9W S7 CS BT. FHDB

38"

(SE. tree is rotting. 67° 58 Z END. SPIKE NAIL L.S.C. DIST TO NAIL

BEARING ON FOUND  
1967 TAG  
IS CORRECT

NEW REFERENCE:

A 5/8" x 30" I.R. WITH DCSO YELLOW PLASTIC CAP, SET PROT. 3"; BEARS N59°W, 12 1/2 FT. DISTANT  
MONUMENT IS ON STEEP SSW SLOPE IN OLD GROWTH FIR FOREST  
MONUMENT IS APPROX. 150 FT. WEST FROM GRAVEL RD.

MINI GIS  
42.81178  
123.81175

5/28/25