



OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

70-120



Station: 16-D16 T 31 S, R 2 W, Sec 13
 Set By (Agency): BPR
 Date Set: 1928
 Recovered By R.S., S.J.F.
 Date Recovered Feb. 29, 1984
 Recovered By _____
 Date Recovered _____
 Recovered By _____
 Date Recovered _____



VERTICAL CONTROL CORPSCON6 NAVD88 1432.65 FT.

Elevation: 1,429.147 NGS Line # 129 USGS Line # _____ OSHD Line # _____
 Precision: 2nd. Agency: USC&GS Proj. # _____ Date: 1956

HORIZONTAL CONTROL

South Zone State Plane Coordinates: Y(Northing) 448513. X(Easting) 4281841.
 Precision: GIS SCALED Agency: DCSO Proj. # _____ Date: 2014
 Approximate Geographic Position: Latitude _____ Longitude _____

DESCRIPTION and TO REACH


A B.P.R. disk stamped " 16-D16 1928 " set in an 8 inch diameter concrete post protruding 2 inches above the ground.

To Reach:

From the intersection of State Highway #227 and U.S.F.S. road #3101 in T31S,R2W,Sec. 13 proceed southeasterly along State Highway #227 approximately 0.6 miles to monument on right.

From the Drew Store on State Highway 227 at Drew, IN T31S,R2W,Sec.14, proceed approx. 1.2 miles southeasterly along State Highway 227 to monument on right.

SKETCH



Reference Marks:

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.