

OFFICE OF THE  
DOUGLAS COUNTY SURVEYOR


Station: SW COR. B.O.  
Set By (Agency): DCSO  
Date Set: \* 1964  
Recovered By RWS, SJF  
Date Recovered 3/28/86  
Recovered By \_\_\_\_\_  
Date Recovered \_\_\_\_\_  
Recovered By \_\_\_\_\_  
Date Recovered \_\_\_\_\_

T 26 S, R 5 W , Sec 16  
PLSS 300400



260-05W-16-020 26S 05W 16  
SW CORNER

NAD 608323.30 4174459.07  
83 43°18' 5" 123°18'22"



VERTICAL CONTROL

Elevation: \_\_\_\_\_ NGS Line # \_\_\_\_\_ USGS Line # \_\_\_\_\_ OSHD Line # \_\_\_\_\_  
Precision: \_\_\_\_\_ Agency: \_\_\_\_\_ Proj. # \_\_\_\_\_ Date: \_\_\_\_\_

HORIZONTAL CONTROL NAD 27

South Zone State Plane Coordinates: Y(Northing) 608,358.37 X(Easting) 1,253,500.05  
Precision: 1/5,000 Agency: DCSO Proj. # 0002 Date: 1974  
Approximate Geographic Position: Latitude 43°18'06" Longitude 123°18'18"

DESCRIPTION and TO REACH

SKETCH

A 1964 1 1/4 in. o.d. I.P. protrudes 5 in. above ground. We disagree with 1964 corner position and saw 1964 disk off I.P. and set new 1986 BC/I.P. N 43° W, 2.7 feet. See DCSO corner renewal records.

NOTE: Coordinates are to center of 1964 sawed off I.P.

Reference Marks:

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.