

GOVERNMENT CORNER RESTORATION FORM  
DOUGLAS COUNTY SURVEYOR

FILED  
Date: 12-5-2018

By: JC

Corner Form: CS 67/45-26

Field Notes: \_\_\_\_\_

DOUGLAS COUNTY SURVEYOR

TOWNSHIP 29S RANGE 03W SECTION 2

PLSS/GCDB No. 29-03-540700

CORNER DESIGNATION: N. 1/4 Corner of Section 2

DATE: October, 25, 2018

CORNER HISTORY, PREVIOUS RENEWALS OR SURVEYS:


- See DCSO Survey & Corner records for PLSS 29-03-540700.

- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

MONUMENT DETAIL

MONUMENT FOUND (CONDITION AND SOURCE):

- A 1" diam. iron pipe, firmly set, projecting 10" above the ground by J. Byron, Deputy County Surveyor, in 1960 per C.S. File 49/47 with a 2 1/2" brass cap marked as follows:



ACCESSORIES FOUND (CONDITION, SOURCE & RECORD):

An original bearing tree by W.H. Byars in 1881:

- A 34" x 3' tall D. fir stump bears South, 6.6 ft. with a healed blaze. (Rec. 8 lks. to face)

A bearing trees by J. Byron in 1960:

- A 30" x 6' tall cedar snag bears S.63° E., 7.9 ft. with a healed blaze.

A bearing tree by J. Carlson, USBLM Cadastral Surveyor, in 1976:

- A 15" x 2 1/2' tall D. fir stump bears S.1° W., 38.9 ft. with a healed blaze.

A bearing tree by D. Edwards in 1999 per M 133-43:

- A 12" D. fir (top dead) bears S.41° E., 21.8 ft. with scribe marks vis. on a partially healed blaze. (Rec. 21.42 ft.)

NEW ACCESSORIES (PROCEDURES AND DESCRIPTION):

- A 4" hemlock bears S.6° W., 20.1 ft. scribed "X", "CSBT"
- A 14" x 1.6' D. fir stump bears S.71 1/2° W., 10.6 ft. to a 8" galv. spike driven in the center of the stump.
- A 6' metal post bears West, 1.6 ft.

LOCATION & COMMENTS:

All bearing trees have BT tags attached. All new bearing trees have double blazed faces with bearings measured to the center of the tree at the root crown and distances measured to a 2 1/2" PK nail in the side and center of the root crown.

N 526850.337

E 4245414.983

GEODETIC COORDINATES  
LATITUDE: 45° 05' 03.409" N.  
LONGITUDE: 123° 01' 49.471" W.  
ELLIPSOID HEIGHT:  
DATUM: NAD 83, Epoch 2010.00  
SOURCE: Trimble GeoXT 6000  
C091811A

COMPASS DECLINATION: 15° E.  
AGENCY: DCSO  
PARTY CHIEF: S. J. FLAUSE  
WITNESSES: J. LORSUNG  
NOTES: ATTACHED

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

OREGON  
JULY 17, 1981  
KRISTIAN O. DEGROOT  
1941

RENEWAL DATE: 12-31-2019

CS 67/45-26

PLSS: 546700

T29S R3W S2  
N1/4 S2

10-25-18

S.J.F. & J.L.

MONUMENT:

A 1" DIA IP WITH 2 1/2" DC50. BC  
FIRMLY SET, MARKED PER RECORD

FOUND: - Healed Blazes

- CARLSON 1976

Orig - 34" x 3' FIR STUMP, SOUTH, 5 29 (FACE) 6.6 CENT

Byrd 30" x 6' CEDAR STUMP, S 63° E, 7 92

~~Carlson~~ 25" x 2 1/2' FIR STUMP, S 1° W, 38 94

- Edwards 1999

12" FIR, S 41° E, 21.42 (FACE)  
(Scribe Vis) 21.8 CENTER

NEW:

4" HEMLOCK, S 6° W, 20' - FT  
" " X " " " CSBT "

14" x 1 1/2" D. FIR STUMP, S 71 1/2° W, 10 6  
w / 8" SPIKE

6' METAL POST, 1 6, WEST

CS 67/45-26