

OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

Station: SE COR

T 29 S, R 5 W , Sec 22

Set By (Agency): BLM

500300

Date Set: 1957

Recovered By RS, PB



Date Recovered 11/14/83

Recovered By _____

Date Recovered _____

Recovered By _____

Date Recovered _____



290-05W-22-001 29S 05W 22
SE CORNER

NAD 508106.02 4181751.78
83 43° 1'38" 123°15'59"

VERTICAL CONTROL

Elevation: _____ NGS Line # _____ USGS Line # _____ OSHD Line # _____

Precision: _____ Agency: _____ Proj. # _____ Date: _____

HORIZONTAL CONTROL OCS 27

South Zone State Plane Coordinates: Y(Northing) 508,141.68 X(Easting) 1,260,793.17

Precision: 1/10,000 Agency: DCSO Proj. # 2008 Date: 1978

Approximate Geographic Position: Latitude 43°01'39" Longitude 123°15'54"

DESCRIPTION and TO REACH

SKETCH

DESCRIPTION: "T29S R5W"

A disk stamped

<u>S22</u>	<u>S23</u>
<u>S27</u>	<u>S26</u>

 set on
1957

a 2 1/2 in. I.P. protruding 4 in. above ground.

TO REACH:

From the intersection of SE Division St.
(Co. Rd.#18) and Cherie Ln. in T29S,R5W,
Sec.27 (in Myrtle Creek), proceed easterly along
SE Division St. 359 ft. to monument on right,
53 ft. from the centerline of ~~SE~~ Division St..

NOTE: See DCSO Corner Renewal notes.

Reference Marks:

Note: For further information, contact the Douglas County Surveyor's Office, Room 205
Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas
County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.