

OFFICE OF THE  
DOUGLAS COUNTY SURVEYOR

Station: WIT. COR. E 1/16 T 31 S, R 4 W, Sec 28

Set By (Agency): BLM

Date Set: 1972

Recovered By JP, RS

Date Recovered 9/14/83


Recovered By \_\_\_\_\_

Date Recovered \_\_\_\_\_

Recovered By \_\_\_\_\_

Date Recovered \_\_\_\_\_

360240



310-04W-28-002 31S 04W 28  
WC E 1/16

NAD 442202.58 4203871.12  
83 42°50'55" 123°10'33"

VERTICAL CONTROL

Elevation: 1,771.221 NGS Line # \_\_\_\_\_ USGS Line # \_\_\_\_\_ OSHD Line # \_\_\_\_\_

Precision: 2nd Agency: DCSO Proj. # 2006 Date: 1973

HORIZONTAL CONTROL

South Zone State Plane Coordinates: Y(Northing) 442,238.91 X(Easting) 1,282,912.27

Precision: 1/25,000 Agency: DCSO Proj. # 2006 Date: 1973

Approximate Geographic Position: Latitude 42°50'55" Longitude 123°10'28"

DESCRIPTION and TO REACH

SKETCH


DESCRIPTION:

A standard corner brass cap stamped  
"W.C. E1/16 C---C S28 1972", protruding  
6 in. above ground.

TO REACH:

From the intersection of McGinnis Creek Rd.  
(BLM Rd. #31-4-27) and Upper Cow Creek  
(Co. Rd. #36) in T31S,R4W,Sec.27, proceed  
westerly along Co. Rd. #36 0.60 miles to  
monument on left.

NOTE: Monument will be under water when  
dam is built.



Reference Marks:

Note: For further information, contact the Douglas County Surveyor's Office, Room 205  
Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas  
County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.