

OFFICE OF THE  
DOUGLAS COUNTY SURVEYOR

Station: A253 T 27 S, R 5W, Sec 19

Set By (Agency): USC&GS & OREG. GEOD. S.

Date Set: 1934

Recovered By KR, TP


Date Recovered 5/82

Recovered By DCSO 7/98; 10/98

Date Recovered \_\_\_\_\_

Recovered By \_\_\_\_\_

Date Recovered \_\_\_\_\_



a-012  
A 253

275 SW 19

NAD 576136.27 4163930.87  
83 43°12'44" 123°20'30"

VERTICAL CONTROL NGVD 29 CORPCON 6 NAVD 88 451.71 FT  
Elevation: 448.231 NGS Line # 94 USGS Line # \_\_\_\_\_ OSHD Line # \_\_\_\_\_  
Precision: 1st Agency: USC&GS Proj. # \_\_\_\_\_ Date: 1956

HORIZONTAL CONTROL NAD 27  
South Zone State Plane Coordinates: Y(Northing) 576,171.48 X(Easting) 1,242,972.56  
Precision: 1/20,000 Agency: DCSO Proj. # 2005-2 Date: 1983  
Approximate Geographic Position: Latitude 43°12'45" Longitude 123°20'25"

DESCRIPTION and TO REACH


SKETCH

DESCRIPTION:

A USC&GS disk stamped "A253 477.557"  
set flush in a concrete sidewalk of  
a bridge.

TO REACH:

Go to the SE end of bridge crossing  
Deer Creek on SE Jackson St.



Reference Marks:

Note: For further information, contact the Douglas County Surveyor's Office, Room 205  
Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas  
County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.