

OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

Station: A 609 T 32 S, R 5W , Sec 21

Set By (Agency): OSHD

Date Set: 1967

Recovered By RWS, SJF


Date Recovered 1/24/85

Recovered By _____

Date Recovered _____

Recovered By _____

Date Recovered _____



a-018
A 609 32S 5W 21

NAD 416689.40 4172666.45
83 42°46'33" 123°17'20"

VERTICAL CONTROL

CORPCON 6 NAVD 88 1542.395 FT

Elevation: 1538.98 NGS Line # _____ USGS Line # _____ OSHD Line # 369

Precision: 3rd Agency: OSHD Proj. # _____ Date: 1980

HORIZONTAL CONTROL

South Zone State Plane Coordinates: Y(Northing) 416,725.61 X(Easting) 1,251,707.78

Precision: 1/25,000 Agency: DCSO Proj. # 2013 Date: 1985

Approximate Geographic Position: Latitude 42° 46' 33" Longitude 123° 17' 16"

DESCRIPTION and TO REACH


DESCRIPTION:

An OSHD disk stamped "A 609 1967" set in SW corner of concrete drain inlet box.

TO REACH:

From the Quines Creek Rd. overcrossing of Interstate Highway 5 in T32S,R5W,Sec.22, proceed southwesterly along Interstate Highway 5 approximately 0.5 miles to monument on left, in median strip. (Quines Creek Rd. is Interstate Highway 5 Exit 86)

SKETCH



Reference Marks:

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.