

A-026

4/82

OFFICE OF THE

9-026  
ACE


255 124 7

DOUGLAS COUNTY SURVEYOR

NAJ  
85

754081.09  
43°40'37"

2748007.31  
124°10'48"



T 22 S, R 12 W, Sec. 7

Station: ACE

Set By (Agency): DCSO (marked)

Date: 1980

CORCON 6 NAVD 08 15,103 FT

VERTICAL CONTROL

Elevation: 11.523 NGS(USC&GS) Line # \_\_\_\_\_ USGS Line # \_\_\_\_\_

Order Of Precision 2nd Agency: DCSO Proj. #: 2007 CS 61/16 Date: 1981

HORIZONTAL CONTROL


Oregon State Plane Coordinates: Y(Northing) 754,116.60 X(Easting) 1,027,046.64  
(South Zone)

Order Of Precision 1/15,000 Agency: DCSO Proj. #: 2008 Date: 1980  
CS 61/16

Approximate Geographic Position: Latitude= 43° 40' 38" Longitude= 124° 10' 44"

DESCRIPTION: Station mark is a bronze disk stamped "DCSO ACE 1980". Cap is set in concrete curb at North end of planter, N. of most S'thly restroom facility in camping-parking area. Cap is 2½ ft. W'stly of West edge of sidewalk at center of parking facility. See sketch.

VICINITY: Winchester Bay - Salmon Harbor between East and West basin.



NOTE: For Possible Further Information On This Station, Please Contact The Douglas County Surveyors Office, Rm. 205 Douglas County Justice Bldg., Roseburg, OR. 97470 Phone 672-3311 Ext. 272. Douglas County residents outside the Roseburg calling area dial toll free 1-800-452-0991.