

OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

Station: ADAM T 22 S, R 4 W, Sec 31

Set By (Agency): DCSO

Date Set: 1978

Recovered By RWS, SJF


Date Recovered 9/87 4/97

Recovered By FD OK 5/03 RWS, SJF

Date Recovered _____

Recovered By _____

Date Recovered _____



a-029
ADAM

22S 4W 31

NAD 720385.86 4201511.35
83 43°36'41" 123°13' 5"

VERTICAL CONTROL NGVD 29 CORPCON 6 NAVD 88 464.41 FT

Elevation: 460⁷⁸ NGS Line # _____ USGS Line # _____ OSHD Line # _____

Precision: 3rd Agency: DCSO Proj. # CS 66/54 Date: 1997

HORIZONTAL CONTROL OCS 27

South Zone State Plane Coordinates: Y(Northing) 720,420.46 X(Easting) 1,280,550.95

Precision: 1/25,000 Agency: DCSO Proj. # ES 60/23, 2010-6 Date: 1978

Approximate Geographic Position: Latitude 43°36'41" Longitude 123°13'01"


DESCRIPTION and TO REACH

SKETCH

A standard DCSO disk stamped "ADAM 1978" in an 8 inch o.d. concrete filled bell-tile set flush with ground.

TO REACH:

Monument is at the intersection of Interstate Highway 5 Frontage Rd. (Co. Rd. #8), Scotts Valley Rd. (Co. Rd. #8), and the I-5 on-ramp in T22S, R4W, Sec. 31.



Reference Marks:

A standard DCSO disk stamped "ADAM RM 1 1978" set in an 8 inch o.d. concrete filled bell-tile protruding approximately 2 inches above the ground bears N75°08'53"W, 327.50 feet (Grid).

A standard DCSO disk stamped "ADAM RM 2 1978" set in an 8 inch o.d. concrete filled bell-tile flush with ground bears S00°11'21"W, 125.51 feet (Grid).

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.