

OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

Station: Airway Beacon 43 Reset T 22 S, R 5W , Sec 20

Date Set: 1957

Set By (Agency): USC & GS

Date Recovered: 7-11-91


Recovered By: TF

Date Recovered: _____

Recovered By: _____

Date Recovered: _____

Recovered By: _____



A-038 22S 5W 20
AIRWAY BEACON 43 RESET

NAD 731303.05 4173079.32
83 43°38'19" 123°19'37"

VERTICAL CONTROL

Elevation: 1796.3 NGS Line # _____ USGS Line # _____ OSHD Line # _____

Precision: GPS Agency: DCSO Proj. # 2008 Date: 1991

HORIZONTAL CONTROL

South Zone O.C.S. 27: Y(Northing) 731,337.82 X(Easting) 1,252,118.90

South Zone O.C.S. 83: Y(Northing) _____ X(Easting) _____

Precision: 1/25,000 Agency: DCSO Proj. # GPS 27/83 Date: 1991


Approx. NAD 83 Geographic Position: Latitude _____ Longitude _____

DESCRIPTION and TO REACH

SKETCH

Found: A Triangulation sta. disk set into the top of the prefabricated concrete post imbedded in the ground.

To reach: From the intersection of St. Hwy. 38 and Drain Yoncalla Hwy. (Co. Rd. #389) in T22S, R5W, S. 17 proceed west on Hwy. 38 for 1.0 mi. to Hayhurst Rd. on the left. turn lt. and proceed southerly on Hayhurst. Rd. for 1.2 mi. to a gravel rd. on the lt. Turn lt. on gravel rd. and proceed easterly over cattle guard and past a gravel stock yard on rt. for .10 mi. to a locked gate . (Key to gate may be obtained at the BLM District Office in Roseburg, Ph. 672-4491, or from Woolley Enterprises in Drain, Ph. 836-2144) Proceed through gate and continue for 1.4 mi. to a sharp hairpin fork lt. turn lt and acend for .7 mi. to sta. mark at summit of hill.



Reference Marks:

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.