

OFFICE OF THE  
DOUGLAS COUNTY SURVEYOR

Station: B 536 T 30 S, R 5 W , Sec 27

Set By (Agency): OSHD

Date Set: 1955

Recovered By RWS, SJF


Date Recovered 1/30/85

Recovered By \_\_\_\_\_

Date Recovered \_\_\_\_\_

Recovered By \_\_\_\_\_

Date Recovered \_\_\_\_\_



B-012  
B 536

30S 5W 27

NAD 471842.12 4177968.19  
83 42°55'39" 123°16'33"

VERTICAL CONTROL NGVD 29 CORPCON 6 NAVD 88 752,32 FT

Elevation: 748.93 ft. NGS Line # \_\_\_\_\_ USGS Line # \_\_\_\_\_ OSHD Line # 369

Precision: 3rd Agency: OSHD Proj. # \_\_\_\_\_ Date: 1980

HORIZONTAL CONTROL DCS 27

South Zone State Plane Coordinates: Y(Northing) 471,877.99 X(Easting) 1,257,009.55

Precision: 1/25,000 Agency: DCSO Proj. # 2008 Date: 1991


Approximate Geographic Position: Latitude \_\_\_\_\_ Longitude \_\_\_\_\_

DESCRIPTION and TO REACH

An OSHD disk stamped "B 536 1955"  
Set flush in the southeast corner  
of a concrete bridge over Canyon Creek.

From the intersection of State Hwy. 99 (Main  
Street) and State Hwy. 227 in Canyonville,  
T 30 S., R 5 W., Sec. 27, proceed easterly  
along State Hwy. 227, 0.15 miles to bridge  
over Canyon Creek and monument in  
southeast corner.

SKETCH



Reference Marks:

Note: For further information, contact the Douglas County Surveyor's Office, Room 205  
Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas  
County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.