

OFFICE OF THE  
DOUGLAS COUNTY SURVEYOR

B-060




b-060  
BM-2

NAD 88 649651.76 4179079.33  
43°28'12" 123°17'47"

Station: BM-3  
Set By (Agency): DCPW  
Date Set: 1977  
Recovered By RWS,SJF  
Date Recovered 9/3/87  
Recovered By \_\_\_\_\_  
Date Recovered \_\_\_\_\_  
Recovered By \_\_\_\_\_  
Date Recovered \_\_\_\_\_

T 24 S, R 5 W , Sec 21



VERTICAL CONTROL CORPCOM 6 NAVD 88 594.85 FT

Elevation: 591.33 NGS Line # \_\_\_\_\_ USGS Line # \_\_\_\_\_ OSHD Line # \_\_\_\_\_  
Precision: 3rd Agency: DCPW Proj. # Pollack Crk. Date: 1977

HORIZONTAL CONTROL

South Zone State Plane Coordinates: Y(Northing) 669,686.40 X(Easting) 1,258,120.23  
Precision: 1/25,000 Agency: DCSO Proj. # 2010-4,CS59/47 Date: 1978  
Approximate Geographic Position: Latitude 43°28'13" Longitude 123°17'43"


DESCRIPTION and TO REACH

A DCPW disk stamped "BM-3" set in a 6 in. dia. concrete filled plastic pipe protruding 8 in. above ground.

TO REACH:

From the intersection of South Cabin Creek Rd. (Co.Rd. #285) and Goodrich Highway (Co.Rd. #29) in T24S,R5W,Sec.20, proceed easterly along Goodrich Road approx. 1.0 miles to a sharp curve turning north and a gravel road(BLM Rd.#24-5-21) running south, monument is southeast of intersection.

SKETCH



Reference Marks:

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.