


OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

Station: BM 500 T 27 S, R 6 W, Sec 12
 Set By (Agency): USGS
 Date Set: 1903
 Recovered By KR, TP
 Date Recovered 6/82
 Recovered By RWS/SJP 1/08/01
 Date Recovered _____
 Recovered By _____
 Date Recovered _____



b-067
BM 500

27S 6W 12

NAD 583882.89 4160669.99
83 43°13'60" 123°21'17"

VERTICAL CONTROL NAVD 29 CORPCON 6 NAVD 88 504.80 FT
 Elevation: 501.328 NGS Line # 6 USGS Line # 146 OSHD Line # _____
 Precision: 1st Agency: USC&GS Proj. # _____ Date: 1957

HORIZONTAL CONTROL OCS 27
 South Zone State Plane Coordinates: Y(Northing) 583,918.05 X(Easting) 1,239,711.69
 Precision: 1/20,000 Agency: DCSO Proj. # 2005-2 Date: 1983
 Approximate Geographic Position: Latitude 43°14'00" Longitude 123°21'13"

DESCRIPTION and TO REACH


SKETCH

DESCRIPTION:

A USGS disk stamped "500 FT DATUM B BM" set in a 1 1/2 ft. diam. concrete post protruding 1 1/2 ft. above ground.

TO REACH:

From the intersection of Airport Rd. and Stewart Parkway proceed northerly along Airport Rd. approx. 0.2 miles. to monument on left.



REFERENCE MARKS 1 & 2 DESTROYED

SET DCSO DRILL CAP IN NEW CONCRETE CURB
 "BM 500 RM 3 2001". ELEVATION 504.74 FEET
 THIRD ORDER

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.