



OFFICE OF THE
DOUGLAS COUNTY SURVEYOR
B-068



Station: BM 964.25 T 29 S, R 3 W, Sec 19
Set By (Agency): U.S.G.S.
Date Set: 1953
Recovered By RS, SJF
Date Recovered June 18, 1984
Recovered By DCSO 11/1992
Date Recovered _____
Recovered By _____
Date Recovered _____



VERTICAL CONTROL CORPSCON6 NAVDB8 967.69 FT.
Elevation: 964.25 NGS Line # _____ USGS Line # 145 OSHD Line # _____
Precision: 3rd Order Agency: DCSO Proj. # 2007 Date: 1992

HORIZONTAL CONTROL CS66/47
South Zone State Plane Coordinates: Y(Northing) 508167 X(Easting) 4221794
Precision: GIS SCALED Agency: DCSO Proj. # _____ Date: 2014
Approximate Geographic Position: Latitude 43° 01' 52" Longitude 123° 06' 54"

DESCRIPTION and TO REACH


SKETCH

A 1X1 inch chisled square in the west end of the north curb of a small concrete bridge over Wiley Creek.

TO REACH:

From the intersection of South Myrtle Rd. (Co. Rd. #18) and Louise Creek-Road (Co. Rd. #176) in T29S, R4W, Sec. 24 proceed easterly along South Myrtle Road approximately 1.65 miles to monument on left.

NOTE: STATION NAME HAS CHANGED AS ELEVATION REVISED. PREVIOUS STATION NAMES HAVE BEEN BM 964.10 IN 1956 AND BM 964.30 IN 1974.



Reference Marks:

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.