



OFFICE OF THE
DOUGLAS COUNTY SURVEYOR



B-070

Station: BM 1130.03 T 29 S, R 3 W, Sec 16
 Set By (Agency): U.S.G.S.
 Date Set: 1953
 Recovered By RS, SJF
 Date Recovered June 18, 1984
 Recovered By DCSO 12/1992
 Date Recovered _____
 Recovered By _____
 Date Recovered _____



VERTICAL CONTROL CORPSCON6 NAVD88 1133.52 FT.

Elevation: 1130.03 ft. NGS Line # _____ USGS Line # 145 OSHD Line # _____

Precision: 3rd Order Agency: DCSO Proj. # 2007 Date: 1992

HORIZONTAL CONTROL

South Zone State Plane Coordinates: Y(Northing) 513453 X(Easting) 4235220

Precision: GIS SCALED Agency: DCSO Proj. # _____ Date: 2014

Approximate Geographic Position: Latitude 43° 02' 48" Longitude 123° 03' 57"


DESCRIPTION and TO REACH

SKETCH

A chisled 1 1/2 X 1 1/2 inch square
in the east end of the south concrete
headwall of a box culvert.


TO REACH:

From the intersection of South Myrtle
Road (County Rd. #18) and Weaver Creek
Road (B.L.M. Rd. #293-16) in T29S, R3W, Sec.16
proceed easterly along County Rd. #18
approximately 0.1 miles to monument on right.
Monument lies on easterly end of south head-
wall of a box culvert, 7 Ft. lower than road
surface. Box culvert is Weaver Creek crossing.



NOTE: STATION NAME HAS CHANGED AS ELEVATION
REVISED. PREVIOUS STATION NAMES HAVE BEEN
BM 1229.94 FROM 1956 AND BM 1129.13 FROM
1974.

SOUTH MYRTLE RD.
(CO. RD. #18)



Reference Marks:

Note: For further information, contact the Douglas County Surveyor's Office, Room 205
Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas
County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.