

Set By (Agency): DCPW

Date Set: 1980

Recovered By RWS, SJF



Date Recovered 2/18/86

Recovered By DCSO/1998

Date Recovered _____

Recovered By _____

Date Recovered _____



DESIGNATION B-109

VERTICAL CONTROL CORPSCON6 NAVD88 801.94 FT.

Elevation: 798.51 NGS Line # _____ USGS Line # _____ OSHD Line # _____

Precision: 3rd Agency: DCSO Proj. # 66/50 Date: 1998

HORIZONTAL CONTROL (798.29 PER DCPW 1980)

South Zone State Plane Coordinates: Y(Northing) 514591 X(Easting) 4105077

Precision: GIS SCALED Agency: DCSO Proj. # _____ Date: 2014

Approximate Geographic Position: Latitude 43° 02' 16" Longitude 123° 33' 09"


DESCRIPTION and TO REACH

A DCPW disk stamped "BC-2 ELEV. 798.29 B.M." set flush in concrete wingwall of bridge over Berry Creek.

From the intersection of Upper Olalla road (Co. Rd. #38) and the gravelled access road to Berry creek dam structure (Ben Irving Reservoir) in T29S, R7W, Sec.20 proceed northwesterly along graveled access Rd. approximately 0.3 miles to bridge over Berry creek and monument in NE wing wall.

From the intersection of Upper Olalla road (Co. Rd. #38) and Hoover Hill Rd. (Co. Rd. #125) in T29S, R7W, Sec.8, proceed southerly along Co. Rd. #38 approx. 2.2 miles to the access road of Berry creek dam structure. (see above to reach)

Reference Marks:



Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.