


OFFICE OF THE

DOUGLAS COUNTY SURVEYOR

B-160



Station: BENIRE

T 29 S, R 7W, Sec 6


Date Set: 1999

Set By (Agency): DCSO

Date Recovered: 7-5-99

Recovered By: RWS SIF

- Found
- New
- Reset
- Not Found
- Referenced
- Destroyed



B-160

VERTICAL CONTROL CORPSCON6 NAVD88 708.83 FT.

Elevation: 705.40 NGS Line # _____ USGS Line # _____ OSHD Line # _____

Precision: 3rd Agency: DCSO Proj. # 2007 Date: 1999

HORIZONTAL CONTROL

CS 66/50

South Zone O.C.S. 27: Y(Northing) _____ X(Easting) _____

South Zone O.C.S. 83: Y(Northing) 532593 X(Easting) 4101128

Precision: GIS SCALED Agency: DCSO Proj. # _____ Date: 2014

Approx. NAD ⁸³ Geographic Position: Latitude 43° 05' 12" Longitude 123° 34' 11"

DESCRIPTION and TO REACH

A DCSO BRASS CAP STAMPED "BENIRE 1999"
SET IN A 6" BY 42" LONG CONCRETE FILLED
BELL TILE PROTRUDING " ABOVE GROUND

GO TO THE INTERSECTION OF BENEDICT ROAD
(CORP #141) AND STATE HWY 42 IN T 29S R7W
SEC 6 MONUMENT IS SOUTH OF INTERSECTION.

APPROX 0.2 MILES SOUTHERLY OF
TEN MILE STORE.

Reference Marks:

