

R 041022A


DOUGLAS COUNTY SURVEYOR'S OFFICE

Designation: B-183 Station: BEND-2 T 24S R 7W S 30 1/4 SE

Date Set: 2003 Set by (Agency): DCSO

Date Recovered: 4-10-03 Recovered by: RWS SJF

- Found  New  Reset
- Not Found  Referenced  Destroyed



VERTICAL CONTROL

NGVD 29 Elevation: 314.35 Feet File # CS 67/2  
 Precision: 3rd Agency: DCSO Project: 2007 Date: 2003  
 NAVD 88 Elevation: 317.84 FT. File # \_\_\_\_\_  
 Precision: CORPSCONB NAVD88 Agency: \_\_\_\_\_ Project: \_\_\_\_\_ Date: \_\_\_\_\_

HORIZONTAL CONTROL - south zone

N _____	E _____	Datum/Adj.: <u>1927</u>	Precision: <u>SCALED</u>
Lat: <u>43° 27' 07"</u>	Long: <u>123° 33' 59"</u>	Agency: <u>DCSO</u>	File # <u>67/2</u> Date: <u>2003</u>
N <u>665572</u>	E <u>4106912</u>	Datum/Adj.: <u>83</u>	Precision: <u>GIS SCALED</u>
Lat: _____	Long: _____	Agency: <u>DCSO</u>	File # _____ Date: <u>2014</u>
N _____	E _____	Datum/Adj.: _____	Precision: _____
Lat: _____	Long: _____	Agency: _____	File # _____ Date: _____
N _____	E _____	Datum/Adj.: _____	Precision: _____
Lat: _____	Long: _____	Agency: _____	File # _____ Date: _____

DESCRIPTION AND TO REACH

DCSO BRASS CAP STAMPED "BEND-2  
2003" SET IN AN 8" DIA. CONCRETE  
FILLED BELLTILE SET FLUSH  
WITH GROUND  
FROM THE INTERSECTION OF TYEE ROAD  
(CO. RD # 33) AND TYEE BRIDGE ACCESS  
ROAD (BLM RD # 25-75.1) IN T 25S,  
R 7W, SEC. 5, PROCEED NORTHERLY  
ALONG TYEE RD 1.35 MILES TO  
INDIAN BEND ROAD ON LEFT, PROCEED  
NORTHERLY ON INDIAN BEND  
ROAD 0.25 MILES TO INTERSECTION,  
PROCEED NORTHERLY ALONG RIGHT  
FORK 0.6 MILES TO MONUMENT  
ON RIGHT.

