

OFFICE OF THE
DOUGLAS COUNTY SURVEYOR


C-001



C-001
C-1

NAD 83 579410.33 43°13'11" 4148854.60 123°23'55"

Station: C-1 T 27 S, R 6 W, Sec 15
 Set By (Agency): CITY(RSBG)
 Date Set: 1967
 Recovered By JP,RS
 Date Recovered 8/24/83
 Recovered By RWS-SJF
 Date Recovered 2000
 Recovered By _____
 Date Recovered _____



VERTICAL CONTROL NGVD 29 CORPCOM 6 NAVD 88 479.16 FT
 Elevation: 475.69 NGS Line # _____ USGS Line # _____ OSHD Line # _____
 Precision: 3RD Agency: DCSO Proj # 66/38 Date: 2000

HORIZONTAL CONTROL OCS 27
 South Zone State Plane Coordinates: Y(Northing) 579,445.42 X(Easting) 1,227,896.22
 Precision: 1/25,000 Agency: DCSO Proj. # 6012-7 Date: 1977
 Approximate Geographic Position: Latitude 43°13'11.9" Longitude 123°23'50.2"

DESCRIPTION and TO REACH


SKETCH

DESCRIPTION:

A disk stamped "C-1" set flush in concrete post.

TO REACH:

From the intersection of Calkins Rd. (Co. Rd. #144) and Cloake St. (gravel Rd.) proceed southerly along Cloake St. 600 ft. ± to station on left. All in T27S, R6W, Sec. 15.



Reference Marks:

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County resident inside the Roseburg calling area, dial toll free 1-800-452-0991.