


OFFICE OF THE  
DOUGLAS COUNTY SURVEYOR

Station: C-101 T 32 S, R 6 W , Sec 32  
 Set By (Agency): DCSO  
 Date Set: 1973  
 Recovered By RS,JP,JRL  
 Date Recovered 8/15/83  
 Recovered By RWS,SJF  
 Date Recovered 8/15/85  
 Recovered By \_\_\_\_\_  
 Date Recovered \_\_\_\_\_



C-006  
C-101

NAD 406903.42 4131032.64  
83 42°44'42" 123°26'33"



VERTICAL CONTROL CORPCON 6 NAVD 88 1439.16 FT

Elevation: 1,435.78 NGS Line # \_\_\_\_\_ USGS Line # \_\_\_\_\_ OSHD Line # \_\_\_\_\_  
 Precision: 3rd Agency: DCSO Proj. # 2006 Date: 1973

HORIZONTAL CONTROL

South Zone State Plane Coordinates: Y(Northing) 406,939.37 X(Easting) 1,210,074.08  
 Precision: 1/25,000 Agency: DCSO Proj. # 2006 Date: 1973  
 Approximate Geographic Position: Latitude 42°44'43" Longitude 123°26'29"

DESCRIPTION and TO REACH


DESCRIPTION:

A DCSO disk stamped "C-101 1973"  
set in a 8 in. diam. concrete  
beltile 3 in. above ground.

TO REACH:

From the intersection of Co.Rd.#177  
(Mount Reuben Rd.) and 7th street in  
Glendale (T33S,R6W,Sec.5) proceed westerly  
along Co.Rd.#177, 0.7 miles to monument  
on right.

SKETCH



Reference Marks: (Proj. #2013)

A DCSO disk stamped "C-101 RM 1 1985"  
bears S 22°36'18" W, 80.84 ft. (grid) elev. 1444.39 ft.

A DCSO disk stamped "C-101 RM 2 1985"  
bears N 30°20'58" W, 51.44 ft. (grid) elev. 1434.62 ft.

Note: For further information, contact the Douglas County Surveyor's Office, Room 205  
Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas  
County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.