

OFFICE OF THE  
DOUGLAS COUNTY SURVEYOR

Station: C-106 T 33 S, R 6 W , Sec 3

Set By (Agency): DCSO

Date Set: 1973

Recovered By RS, PB


Date Recovered 11/3/83

Recovered By \_\_\_\_\_

Date Recovered \_\_\_\_\_

Recovered By \_\_\_\_\_

Date Recovered \_\_\_\_\_



c-011  
C-106

33S 6W 3

NAD 403893.04 4143653.21  
83 42°44'17" 123°23'43"

VERTICAL CONTROL CORPCONG NAVD88 1422.479FT

Elevation: 1419.113 NGS Line # \_\_\_\_\_ USGS Line # \_\_\_\_\_ OSHD Line # \_\_\_\_\_

Precision: 2nd Agency: DCSO Proj. # 2006 Date: 1973

HORIZONTAL CONTROL

South Zone State Plane Coordinates: Y(Northing) 403,929.09 X(Easting) 1,222,694.63

Precision: 1/25,000 Agency: DCSO Proj. # 2006 Date: 1973

Approximate Geographic Position: Latitude 42°44'17" Longitude 123°23'39"

DESCRIPTION and TO REACH


SKETCH

DESCRIPTION:

A DCSO disk stamped "C-106 1973" set in a concrete-filled tile protruding 2 in. above ground and 10 ft. below edge of pavement.

TO REACH:

From the intersection of Glendale Valley Rd. ( Co. Rd. # 313 ) and Twin Pines Rd. ( Co. Rd. # 355 ) in T32S,R6W,Sec.35, proceed westerly along Glendale Valley Rd. 0.7 miles to monument on left.



Reference Marks:

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.