

OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

Station: C-134 T 32 S, R 4 W, Sec 1

Set By (Agency): DCSO

Date Set: 1973

Recovered By RWS


Date Recovered 12/10/81

Recovered By RWS

Date Recovered 8/26/85

Recovered By _____

Date Recovered _____



C-039
C-134 32S 4W 1

NAD 432570.42 4216158.55
83 42°49'24" 123° 7'44"

VERTICAL CONTROL CORPCOM 6 NAVD 88 1916.39 FT

Elevation: 1912.872 NGS Line # _____ USGS Line # _____ OSHD Line # _____
Precision: 2nd Agency: DCSO Proj. # 2006 Date: 1973

HORIZONTAL CONTROL

South Zone State Plane Coordinates: Y(Northing) 432,606.86 X(Easting) 1,295,199.66
Precision: 1/25,000 Agency: DCSO Proj. # 2006 Date: 1973
Approximate Geographic Position: Latitude 42°49'24" Longitude 123°07'39"

DESCRIPTION and TO REACH


SKETCH

DESCRIPTION:

A DCSO disk stamped "C-134 1973" set flush in a boulder.

TO REACH:

Go to the intersection of Upper Cow Crk. Rd.
(Co. Rd. #36) and Hauck Ranch Rd. (BLM Rd.#32-4-1)
in T32S,R4W,Sec.1.



Reference Marks: (Proj. #2013)
A DCSO disk stamped "C-134 RM 1 1985"
bears N 71°45'30" W, 94.47 ft. (grid) elev. 1921.807 ft.
A DCSO disk stamped "C-134 RM 2 1985"
bears S 0°47'53" W, 22.50 ft. (grid) elev. 1898.998 ft.

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.