


C-051

OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

C-051
C 594

215 4W 32

NAD 752740.91 4206376.72
83 43°42' 1" 123°12' 14"



T 21 S, R 4W, Sec. 32

Station: C 594

Set By (Agency): OSHD

Date: 1965

CORPCON 6 NAVD 88
540.09 FT

NGVD 29

VERTICAL CONTROL

Elevation: 536.42 NGS(USC&GS) Line # _____ ~~USGS~~ Line # 369

Order
Of Precision 3rd Agency: OSHD Proj. #: _____ Date: 1977

HORIZONTAL CONTROL

OCS 27


Oregon State Plane Coordinates: Y(Northing) 752,775.61 X(Easting) 1,285,415.78
(South Zone)

Order
Of Precision 1/25,000 Agency: DCSO Proj. #: 2008 Date: 1979

Approximate Geographic Position: Latitude= 43°42'02" Longitude= 123°12'09"

DESCRIPTION: Monument is a OSHD disk in con-
crete monument 88ft. W. of SB centerline,
1.5 ft. E. of B.M. witness post, cap is
flush with ground and approx. same elevation
as pavement.

SKETCH



BM 1 S 66° 25' 28" W 150.46'
BM 2 N 23° 45' 11" W 349.59'

VICINITY: Approx. 2.03 mi. S. of Curtin
along I-5, approx. M.P. 161.4.

NOTE: For Possible Further Information On This Station, Please Contact The Douglas County Surveyors Office, Rm. 205 Douglas County Justice Bldg., Roseburg, OR. 97470 Phone 672-3311 Ext. 272. Douglas County residents outside the Roseburg calling area dial toll free 1-800-452-0991.