



OFFICE OF THE  
DOUGLAS COUNTY SURVEYOR

Station: CHING T 28 S, R 7W, Sec 1  
Set By (Agency): DCSO  
Date Set: 1985  
Recovered By RWS, SJF  
Date Recovered 3-4-85  
Recovered By \_\_\_\_\_  
Date Recovered \_\_\_\_\_  
Recovered By \_\_\_\_\_  
Date Recovered \_\_\_\_\_



C-082

NGVD 29



VERTICAL CONTROL

Elevation: 567.228 ft. NGS Line # \_\_\_\_\_ USGS Line # \_\_\_\_\_ OSHD Line # \_\_\_\_\_  
Precision: 2nd Agency: DCSO Proj. # 2013 Date: 1985

HORIZONTAL CONTROL CORPSCON6 NAVD88 570.68 FT. C566/61

South Zone State Plane Coordinates: Y(Northing) 560886 X(Easting) 9125631

Precision: G15 SCALED Agency: DCSO Proj. # \_\_\_\_\_ Date: 2014

Approximate Geographic Position: Latitude 43°10' 00" Longitude 123° 28' 54"

DESCRIPTION and TO REACH


SKETCH

DESCRIPTION:

A DCSO disk stamped "CHING 1985"  
set flush in the southwest corner  
of bridge over a small tributary  
of Lookingglass Creek.

TO REACH:

From the intersection of Brockway, Lookingglass Rd. (Co. Rd. #47) and Dairy Loop Rd. (Co. Rd. #108) in T28S, R7W, Sec. 2; proceed easterly along Brockway-Lookingglass Rd. 0.15 miles to a bridge over a small tributary of Lookingglass Creek and monument on right.



Reference Marks:

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.