

OFFICE OF THE  
DOUGLAS COUNTY SURVEYOR

Station: CLELL T 28 S, R 5 1/2 E, Sec 30 UNS

Set By (Agency): DCSO

Date Set: 1974

Recovered By FLI (DCSO)


Date Recovered 7-25-84

Recovered By O.D.O.T.

Date Recovered 9-10-98 **FD OK**

Recovered By \_\_\_\_\_

Date Recovered \_\_\_\_\_



C-090  
CLELL

28S 51/2E 30

NAD 533338.14 4477690.98  
83 43° 7' 5" 122° 9' 41"

VERTICAL CONTROL NGVD 29 CORPCOM 6 NAVD88 5245.147 FT

Elevation: 5240.775 NGS Line # \_\_\_\_\_ USGS Line # \_\_\_\_\_ OSHD Line # \_\_\_\_\_

Precision: 2nd Agency: DCSO Proj. # 2004-8 CS57/23 Date: 1974

HORIZONTAL CONTROL OCS 27

South Zone State Plane Coordinates: Y(Northing) 533,376.25 X(Easting) 1,556,729.67

Precision: 1/25,000 Agency: DCSO Proj. # 2004-8 CS57/23 Date: 1975


Approximate Geographic Position: Latitude 43°07'05" Longitude 122°09'37"

DESCRIPTION and TO REACH

SKETCH

1.6 miles SW along new Highway  
230 from junction of new Hwy 138  
and new Hwy 230.

Brass cap in 6" belltile, 47 ft.  
south of edge of pavement.



Reference Marks:	CLELL R.M. 1	Brass cap in 6" belltile (El. 5240.096)	FOUND 9/10/98 GOOD CONDITION PER ODOT
		533,470.49	
	B.M. A-21	Brass cap in concrete post (El. 5236.523)	
		533,562.71	1,556,766.67

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.