


OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

C-094
CLOVER

26S 5W 36

NAD 592139.26 4190875.89
83 43°15'31" 123°14'33"



T 26 S, R 5W, Sec. 36

Station: Clover

Set By (Agency): USC&GS

Date: 1953

*CORPCOM 6 NAVD 88
2033.7 FT*

NGVD 29

VERTICAL CONTROL

Elevation: 2030.1 NGS(USC&GS) Line # _____ USGS Line # _____

Order
Of Precision VA Agency: DCSO Proj. #: 2002 Date: 1971

HORIZONTAL CONTROL

DCS 27

Oregon State Plane Coordinates: Y(Northing) 592,174.51 X(Easting) 1,269,916.85
(South Zone)

Order
Of Precision 1/100,000 Agency: DCSO Proj. #: 2002 Date: 1971

Approximate Geographic Position: Latitude= _____ Longitude= _____

DESCRIPTION: On hill known as "Roundtop"


Standard disk cemented in the top of an iron
pipe that projects 4" and is 5 ft. S. of White
witness post.

Off Sunshine Rd.

VICINITY: 6.5 mi NE of Roseburg, 6.5 mi.

SE of Wilbur.

SKETCH



NOTE: For Possible Further Information On This Station, Please Contact The Douglas County Surveyors Office, Rm. 205 Douglas County Justice Bldg., Roseburg, OR. 97470 Phone 672-3311 Ext. 272. Douglas County residents outside the Roseburg calling area dial toll free 1-800-452-0991.