


OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

Station: COOBURG 2 T 28 S, R 6 W, Sec 16
 Set By (Agency): NGS
 Date Set: 1974
 Recovered By RS, SIF
 Date Recovered April 6, 1984
 Recovered By _____
 Date Recovered _____
 Recovered By _____
 Date Recovered _____



C-105
COOBURG 2

28S 6W 16

NAD 546395.61 4141321.44
83 43° 7'43" 123°25'21"

VERTICAL CONTROL NGVD 29 CORCON 6 NAVD 88 813. FT
 Elevation: 810 Ft. NGS Line # _____ USGS Line # _____ OSHD Line # _____
 Precision: VA Agency: NGS Proj. # _____ Date: 1974

HORIZONTAL CONTROL OCS 27
 South Zone State Plane Coordinates: Y(Northing) 546,430.72 X(Easting) 1,220,363.16
 Precision: 1/25,000 Agency: DCSO Proj. # 2005 C.S. 56/9 Date: 1974
 Approximate Geographic Position: Latitude 43°07'43" Longitude 123°25'16"


DESCRIPTION and TO REACH

SKETCH

An NGS disk stamped "COOBURG 2 1974" set in a 1 X 1 foot concrete monument flush with ground.

TO REACH:

From the intersection of NW Lookingglass Rd. (Co. Rd. #47) and Galaxy Drive in Winston (T28S, R6W, Sec. 21) proceed northerly along Galaxy Drive approximately 0.15 miles to a cul-de-sac at the end of Drive; proceed northerly on foot approximately 450 feet to top of knoll and monument.



Reference Marks:

An NGS disk stamped "COOBURG 2 NO 4 1974" bears N 32°37'09"E, 29.96 Feet (grid).
 An NGS disk stamped "COOBURG 2 NO 5 1974" bears S75°16'49"W, 44.80 Feet (grid).

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.