

OFFICE OF THE  
DOUGLAS COUNTY SURVEYOR

Station: Cover T 30 S, R 5W , Sec 19

Set By (Agency): DCSO

Date Set: 1978

Recovered By JP-RWS


Date Recovered 2-11-82

Recovered By \_\_\_\_\_

Date Recovered \_\_\_\_\_

Recovered By \_\_\_\_\_

Date Recovered \_\_\_\_\_



c-110  
COVER 30S 5W 19

NAD 478263.28 4162256.35  
83 42°56'37" 123°20' 7"

VERTICAL CONTROL

Elevation: \_\_\_\_\_ NGS Line # \_\_\_\_\_ USGS Line # \_\_\_\_\_ OSHD Line # \_\_\_\_\_

Precision: \_\_\_\_\_ Agency: \_\_\_\_\_ Proj. # \_\_\_\_\_ Date: \_\_\_\_\_

HORIZONTAL CONTROL *OCS 27*

South Zone State Plane Coordinates: Y(Northing) 478,299.00 X(Easting) 1,241,297.79

Precision: 1/25,000 Agency: DCSO Proj. # 2008 Date: 1978


Approximate Geographic Position: Latitude 42°56'38" Longitude 123°20'03"

DESCRIPTION and TO REACH

Found: A standard DCSO disk marked "Cover 1978". Monument is set in a 6" concrete filled belltile protruding 8" from the ground and is 7'± above pavement. Witness sign and post lie 2' NW of monument.

To reach: From center of I-5 overpass in T30S R5W sec. 20 and Riddle access road (Co. Rd. #20A.) proceed toward Riddle along Co. Rd. #20A 0.95 miles to station on the right. (or Northerly side of road.)

SKETCH



Reference Marks:

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.