

OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

Station: DAY AZIMUTH T 29 S, R 3 W, Sec 23

Set By (Agency): DCSO

Date Set: 1978

Recovered By RS, PB



Date Recovered 10/26/83

Recovered By _____

Date Recovered _____

Recovered By _____

Date Recovered _____



d-022 295 3W 23
DAY AZIMUTH

NAD 507217.41 4243068.40
83 43° 1'49" 123° 2'13"

VERTICAL CONTROL

Elevation: _____ NGS Line # _____ USGS Line # _____ OSHD Line # _____

Precision: _____ Agency: _____ Proj. # _____ Date: _____

HORIZONTAL CONTROL **OCS 27**

South Zone State Plane Coordinates: Y(Northing) 507,253.53 X(Easting) 1,322,109.82

Precision: 1/50,000 Agency: DCSO Proj. # 2010-5 CS 60/3 Date: 1979

Approximate Geographic Position: Latitude 43°01'49" Longitude 123°02'09"

DESCRIPTION and TO REACH


SKETCH

DESCRIPTION:

A DCSO disk stamped "DAY AZIMUTH 1978" set in a 6"x36" concrete filled tile flush with the ground.

TO REACH:

From the intersection of Co. Rd. #34 (Day Creek Rd.) and State Hwy. #227 in T30S, R4W, Sec.10, proceed northeasterly along Co. Rd. #34 6.05 miles to a gravel road on right (BLM Rd. #29-3-33.0); proceed northeasterly along BLM Rd. 29-3-33.0 2.2 miles to its intersection with BLM Rd. #29-3-23.1; monument is 820 ft. easterly along BLM Rd. #29-3-33.0 on left.



Reference Marks:

Note: For further information, contact the Douglas County Surveyor's Office, Room 205 Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.