

OFFICE OF THE
DOUGLAS COUNTY SURVEYOR

Station: DERBY T 27 S, R 6 W , Sec 11

Set By (Agency): DCSO

Date Set: 1982

Recovered By TP, KR

Date Recovered 7/82

Recovered By RWS-SJF

Date Recovered 2000; 3/2001

Recovered By ^{OK} SJF-JP 1/2008


Date Recovered _____



d-037
DERBY

27S 6W 11

NAD 585337.75 4156113.38
83 43°14'12" 123°22'19"



VERTICAL CONTROL NGVD 29 CORPSON 6 NAVD88 470.528 FT

Elevation: 467.068 NGS Line # _____ USGS Line # _____ OSHD Line # _____

Precision: 2nd Agency: DCSO Proj. # 2007 Date: 1990

HORIZONTAL CONTROL OCS 27

South Zone State Plane Coordinates: Y(Northing) 585,372.87 X(Easting) 1,235,155.06

Precision: 1/20,000 Agency: DCSO Proj. # 2005-2 Date: 1983

Approximate Geographic Position: Latitude 43°14'13" Longitude 123°22'15"

DESCRIPTION and TO REACH


DESCRIPTION:

A DCSO disk stamped "DERBY 1982"
set flush in concrete curbing.

TO REACH:

From the intersection of Garden Valley
Blvd. and Stewart Parkway proceed northerly
along Stewart Parkway 0.4 miles to entrance
to Mercy Rehab and monument.
(most northerly entrance to Roseburg
Valley Mall)

SKETCH



Reference Marks:

Note: For further information, contact the Douglas County Surveyor's Office, Room 205
Douglas County Justice Building, Roseburg, OR 97470. Phone 440-4278. Douglas
County residents outside the Roseburg calling area, dial toll free 1-800-452-0991.